

**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN                                | RFB Clause                                                                                                                                                                      | Clarifications Sought/Suggestions | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|-----------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>I. Addendum from Employers</b> |                                                                                                                                                                                 |                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| 1                                 | Section II Bid Data Sheet, ITB)<br>Clause No. 31.2                                                                                                                              |                                   | Sub-Clause 31.2 is inserted under Section II-Bid Data Sheet as under:<br><br>"To satisfy the financial resource qualification requirements, including lines of credit, liquid assets, and net worth, a Bidder may rely on the financial capacity of its Parent or Holding Company. In such cases, the Parent or Holding Company shall provide a written undertaking confirming its full financial support to the Bidder for the performance of the Contract. The undertaking shall also include a commitment that, in the event the Bidder fails to perform the Contract after award, the Parent or Holding Company shall assume full responsibility for and execute the remaining works." |
| 2                                 | Section IV Bidding Forms,<br>Appendix to Technical Part of Bid,<br>Construction Schedule                                                                                        |                                   | Under Section IV-Bidding Forms, Appendix to Technical Part of Bid, Construction Schedule, the Word "DCP-III" is amended as "DCP-I"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 3                                 | Section VII Works' Requirement,<br>Environmental and Social(E&S) and<br>OCHS requirements, Contractor's<br>Representative and Key Personnel,<br>B: Key Personnel for ES and OHS |                                   | At the bottom of the table mentioned as Note: i. and ii. under Section VII- Works' Requirement, Environmental and Social(E&S) and OCHS requirements, Contractor's Representative and Key Personnel, B: Key Personnel for ES and OHS are corrected as under:<br><br>i. Resumes of all Key Personnel (SN 1-18) shall be submitted in accordance with Form PER-1 and Form PER-2.<br>ii. For Non-Key Personnel (SN 19-22), where all personnel cannot be identified at the bidding stage, the bidder can choose to submit an undertaking confirming that such personnel will be mobilized if the bid is successful.                                                                            |
| 4                                 | Section IX Particular Conditions<br>Part B Special Provisions Sub Clause<br>4.1                                                                                                 |                                   | In the paragraph under "At the end of the second paragraph of Sub-Clause 4.1, insert" the word "next one month" is hereby replaced as "next three months."                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| 5                                 | Section VII Works' Requirement,<br>Scope of Work                                                                                                                                |                                   | Add the work: Final lining with lighting system complete for 550 m long Highway Tunnel                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN                                                                       | RFB Clause                                                                                                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                       | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|--------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 6                                                                        | Section VII-Works' Requirement, 6. Construction Facilities, 6.2. Land for Contractor's Construction Facilities & Establishment, 6.2.1. Lands |                                                                                                                                                                                                                                                                                                                                                                                                                                         | SN. F (1) MD1 is removed from the available lands.                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 7                                                                        | Section II-Bid Data Sheet                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                         | ITB 25.1 is hereby amended as<br>"The Bid Opening shall take place on at:<br>Venue: Conference Hall, Dorjilung Hydro Power Limited (DHPL), Gyalpoizhing, Mongar, Bhutan<br>Date: July 28, 2026<br>Time: 15.30 hrs. (Bhutan Standard Time)"                                                                                                                                                                                                                                                                              |
| <b>II. Clarifications, Addendum against the queries from the bidders</b> |                                                                                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 1                                                                        | Section II - Bid Data Sheet, ITB. 22.1                                                                                                       | We note that the submission of the technical-economic offer for all three Lots is required by July 28, 3:00 PM. We would like to point out that the six weeks granted are highly inadequate to complete the tender study to a high standard of quality for a project of this complexity and scale. We therefore kindly ask you to favourably consider our request for a four-month extension, from July 28, 2026, to November 28, 2026. | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs.                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 2                                                                        | Section II- Bid Data Sheet, ITB 22.1                                                                                                         | We formally request a minimum two-month extension to the current offer submission deadline of 28 July 2025.                                                                                                                                                                                                                                                                                                                             | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs.                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 3                                                                        | Section II- Bid Data Sheet, ITB 45                                                                                                           | Whether the three packages may be awarded to the same competitor, should it submit the best offer for all of them;                                                                                                                                                                                                                                                                                                                      | Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:<br>The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer. |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                  | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|----|-----------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 4  | Section II - Bid Data Sheet, ITB. 45                                        | Whether the submission of a combined offer, in addition to the three individual offers, will be permitted, allowing us to benefit from the synergies among the three packages.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Refer Section I, ITB 37.3 Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:<br>"The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer." |
| 5  | General                                                                     | We kindly request the most recent DRUK financial statements (FY 2025), to support the standard internal assessments in view of our potential participation in the tender.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | All publicly disclosed reports are available on DGPC website:<br><a href="https://www.drukgreen.bt">https://www.drukgreen.bt</a>                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 6  | Section-III; Evaluation and Qualification Criteria; Cl: 4.1; Page 56 of 319 | In general, major Indian PSU clients (NHPC, THDC, NEEPCO, SJVNL, UJVNL) consider Completed/ Substantially completed projects (i.e., projects with more than 80% completion) as eligible General Construction Experience. References of major PSU projects where such criteria has been followed are enclosed herewith as Annexure-1. In line with the above, we kindly request that substantially completed projects may also be considered towards the General Construction Experience requirement. Accordingly, it is requested to modify the mentioned clause as follows: "i) Civil General Construction Work Experience in the last 20 years with work value of a single completed work / Substantially Completed work (more than 80%) or up to five works more than BTN. 16,100 million". Annexure-1 Project List: • NHPC_Link-3 • NEEPCO_Tato-II • SJVNL_Sunni Dam • THDC_Kalai-II • UJVNL_Lakhwar HEP • KHEL_Kholongchhu HEP | Section-III; Evaluation and Qualification Criteria; Cl: 4.1; Page 56 of 319 is amended as under:<br>"(i) Civil General Construction Work Experience in the last 20 years with work value of a single completed work/Substantially Completed work or up to five works more than BTN. 16,100 million. The substantially completed work shall be evaluated against submission of documentary evidence from the Client/Employer".                                                                                                                       |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                  | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|----|-----------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 7  | Section-III; Evaluation and Qualification Criteria; Cl: 4.1; Page 56 of 319 | In line with the above query, it is requested to modify the mentioned clause as follows:“(ii) Hydro-Mechanical General Construction Work Experience in last 20 years with work value of a single completed work / Substantially Completed work (more than 80%) or up to five works more than BTN. 1,250 million”                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Section III-Evaluation and Qualification Criteria; Sub-Clause: 4.1(ii); Page 56 of 319 is amended as under:<br>"Hydro-Mechanical General Construction Work Experience in last 20 years with work value of a single completed work/Substantially Completed work or up to five works more than BTN. 1,000 million. The substantially completed work shall be evaluated against submission of documentary evidence from the Client/Employer".                                                                                                                                                                                                   |
| 8  | Section-III; Evaluation and Qualification Criteria; Cl:4.2; Page 57 of 319  | <p>In major dam tenders issued in India, the pre-qualification criteria for dam construction experience generally specify the required dam height (e.g., 50% of Dam height or 80 m, preferably the latter), references of similar pre-qualification criteria from major dam project tenders are enclosed herewith as Annexure–2.In line with the above, we kindly request that dam height may be considered as the qualifying criterion for assessment of dam construction experience.Accordingly, it is requested to modify the mentioned clause as follows:“Completion of at least one Concrete Gravity/ Arch dam/RCC Dam of minimum 80 m height.”If the Concrete Quantity requirement cannot be removed, alternatively request to modify the clause as follows:</p> <p>“i) Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.28 million m3 in any one year in a Dam/Weir/Barrage in the last 20 years in a single project.Note: The Dam Height and Concrete Quantity can be met through two different projects.</p> <p>ii) Successfully achieved open excavation for abutments &amp; foundation for the Dam of</p> | <p>Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i) and 4.2(ii) are hereby amended as:</p> <p>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m3 in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.The Dam height and progress of concreting can be met through two separate projects. 4.2(ii)</p> <p>"Successfully achieved excavation for Dam/Barrage/Weir complex for River Diversion of minimum excavation volume of 0.80 million m3 in any one year in the last 20 years in the single project."</p> |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                                           | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                             |
|----|----------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                                      | minimum excavation volume 1.2 million m3 in any one year in the last 20 years in a single project."Annexure-2 Project List:<br>• NHPC_Dibang Dam Pkg<br>• NHPC_Kamala Lot-1<br>• UJVNL_Lakhwar HEP                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                        |
| 9  | Section-III; Evaluation and Qualification Criteria; Cl: 4.2; Page 57 of 319                                          | It is requested to modify the clause as follows:"Successfully carried out radial gate manufacture and erection of size of 80 m2 or more with a minimum head of 35 m complete with hydraulics hoisting system by its own or through Specialized Subcontractor in last 20 years in a single project."                                          | Section-III Evaluation and Qualification Criteria, Sub Clause 4.2(iv), is hereby amended as "Successfully carried out radial gate manufacture and erection of size of 50m2 or more with a minimum head of 30m complete with hydraulics hoisting system by its own or through Specialized Sub-contractor in last 20 years in a single project."                                                         |
| 10 | Section-III; Evaluation and Qualification Criteria; Page 56 of 319                                                   | It is requested to add a clause for Threshold Criteria for Recognition of JV/Consortium Experience in Evaluation of Specific Experience for work.<br>An example of the said clause from various projects are attached as <b>Annexure-3</b> .<br><br>Annexure-3 Project List:<br>• NHPC_Link-3<br>• SJVNL_Sunni Dam<br>• KHEL_Kholongchhu HEP | Under Section-III Evaluation and Qualification Criteria Sub Clause 1.1, the following is added:<br><br>"Where work experience certificate had been issued in the name of JV/Consortium, the JV/Consortium partner shall have at least 35% participation/profit sharing percentage in the JV/Consortium for which full credit of the work executed by the JV/Consortium shall be given to such Bidder." |
| 11 | Section-II; Bid Data Sheet; ITB 15.1; Page 43 of 319<br>Section-IX; Particular Conditions; Cl 14.15; Page 231 of 319 | It is requested to delete the clause mentioned, as the exchange rate fluctuations are beyond the Bidder's control.                                                                                                                                                                                                                           | Provision of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                       |
| 12 | Section-II; Bid Data Sheet; ITB 16.2; Page 43 of 319                                                                 | We understand that there is no minimum limitation category wise.<br>Kindly confirm.                                                                                                                                                                                                                                                          | No category wise limitations                                                                                                                                                                                                                                                                                                                                                                           |
| 13 | Section-II; Bid Data Sheet; ITB 19.1; Page 43 of 319                                                                 | It is requested to accept Bank Guarantees from any Indian Nationalized bank / scheduled bank.                                                                                                                                                                                                                                                | Section II-Bid Data Sheet Sub-Clause 19.1 is hereby amended as:"A Bid Security shall be required. Bid must be accompanied by a Bid Security in the form an unconditional bank guarantee from any financial institution in Bhutan and India. The amount                                                                                                                                                 |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                                                         | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|----|------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                                                    |                                                                                                                                                                                                                                                                                                       | and currency of the Bid Security shall be BTN/INR 248 million (Two Hundred Forty-Eight million) only."                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 14 | Section-II; Bid Data Sheet; ITB 25.1; Page 44 of 319                                                                               | Printing all documents and carrying them to Bhutan is cumbersome. Major Indian PSU's accept electronic bid submission and ask for hard copies only of key originals like EMD BG and PoA.<br>Hence, it is requested to permit online submission of the bid and hard copies only for the key documents. | Provision of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| 15 | Section-II; Bid Data Sheet; ITB 45; Page 46 of 319                                                                                 | It is requested that the bidder be allowed to mutually discuss with the employer and agree on the package from which the bidder wishes to withdraw.                                                                                                                                                   | Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:<br>The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on what was considered the most advantageous outcome for the Employer. |
| 16 | Section-III; Evaluation and Qualification Criteria; Cl 1.5; Page 49 of 319                                                         | It is required to provide some sample evaluation score for scoring based on age of the equipment.                                                                                                                                                                                                     | Refer Section III-Evaluation and Qualification Criteria, Clause 1.5 Minimum Equipment and Machineries Availability. Bidders are encouraged to propose newer equipment and machinery in order to achieve a higher evaluation score under this criterion.                                                                                                                                                                                                                                                                                     |
| 17 | Section-III; Evaluation and Qualification Criteria; Cl 1.5; Page 49 of 319<br><br>Section-VII; Work's Requirement; Page 224 of 319 | There appears to be a discrepancy in the Excavator capacity mentioned in the two clauses. It is requested that the same be clarified.                                                                                                                                                                 | Excavator Bucket Capacity under Section III-Evaluation and Qualification Criteria is corrected as 1.6 to 3 cum                                                                                                                                                                                                                                                                                                                                                                                                                              |
| 18 | Section-III; Evaluation and Qualification Criteria; Cl 1.5; Page 49 of 319                                                         | There appears to be a discrepancy in the Dewatering Pump capacity mentioned in the two clauses.<br>It is requested that the same be clarified.                                                                                                                                                        | Dewatering Pump Capacity under Section III-Evaluation and Qualification Criteria is corrected as 10 to 50 HP                                                                                                                                                                                                                                                                                                                                                                                                                                |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                 | Clarifications Sought/Suggestions                                                                                                                                                    | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|----|----------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    | Section-VII; Work's Requirement; Page 224 of 319                           |                                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 19 | Section-III; Evaluation and Qualification Criteria; Cl 1.7; Page 51 of 319 | It is requested to delete the mentioned clause, as restricting the pages will hinder the Bidder his ability to showcase his comprehensive reports prepared based on his experiences. | Page limit of 50 Pages under Section-III Evaluation and Qualification Criteria, Clause 1.7 (Page 51 of 319) is hereby removed.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| 20 | Section-IV; Bidding Forms; Method Statement; Page 69 of 319                | Bidder understands that the DCP-III activities were mistakenly mentioned in this Bidding Form. It is requested to rectify the same.                                                  | Second Paragraph of Section IV-Bidding Forms (Page 69 of 319) is amended as below:<br>The Method Statement shall cover all aspects of the activities under DCP-I with special emphasize on the following points:<br>1. River Diversion Management plan<br>2. Excavation Sequence of the Cofferdams (both U/s & D/s)<br>3. Cut-Off Diaphragm Wall methodology<br>4. Dam abutment stripping method<br>5. RCC placement method<br>6. Excavation sequence of Heading & Benching Method for Head Race Tunnel<br>7. Tunnel concrete lining arrangements<br>8. Diversion Tunnels Plugging method<br>9. Dewatering plan<br>10. Curtain grouting plan<br>11. Dam Instrumentation Plan<br>12. Cycle time for Cofferdams, RCC & CVC concrete placement method for main dam and tunnel works with work fronts<br>13. Manpower and material mobilization schedule<br>14. Quality Control and Quality Assurance Plan<br>15. Hydro-Mechanical gate erection plan<br>16. Interfacing Plan for Civil and Hydro-Mechanical works<br>17. Innovation and use of latest technology |
| 21 | Section-IV; Bidding Forms; Form of Bid Security; Page 106 of 319           | It is requested to add this NWC clause at the end of Bank Guarantee Form: "Notwithstanding anything contained herein: i. Our liability under this Bank Guarantee shall not exceed    | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                                                                                                                                                                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                             | Addendum and Clarification                                                                                                                                                                                                                                                              |
|----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                                                                                                                                                                                              | _____ .ii. This Bank Guarantee shall be valid up to _____ .iii. We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only and only if Employer serve upon Bank a written claim or demand on or before _____ (@) _____                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                         |
| 22 | Section-VII; Work's Requirement; Cl 8; Page 156 of 319                                                                                                                                                                                                                       | It is requested to provide the KMZ files mentioned in the clause.                                                                                                                                                                                                                                                                                                                                                                             | KMZ file shared as Annexure: DCP-I(a)                                                                                                                                                                                                                                                   |
| 23 | Section-IX; Particular Conditions; Cl 8.8; Page 230 of 319                                                                                                                                                                                                                   | Bidder understands that for delays of less than one week, delay damages shall apply on a pro rata basis                                                                                                                                                                                                                                                                                                                                       | Yes                                                                                                                                                                                                                                                                                     |
| 24 | Section-IX; Particular Conditions; Cl 14.6.2; Page 230 of 319                                                                                                                                                                                                                | It is requested to delete the mentioned clause, as this may delay certification and cash flow for small portion of completed works.                                                                                                                                                                                                                                                                                                           | Clause 14.6.2 of Section-IX Particular Conditions Part A, Contract Data (Page 230 of 319) is hereby amended as "0.25% of the Accepted Contract Amount for the initial period of 1 (one) year from Commencement Date and thereafter 0.50 % of the Accepted Contract Amount shall apply " |
| 25 | Section-IX; Particular Conditions; Cl 14.6.2; Page 255 of 319                                                                                                                                                                                                                | The Delay Damage of 0.35% per week for Milestones seems to be higher when compared to the market trend.<br><br>It is requested to modify the clause in line with Major Indian PSUs:<br>"0.005% of the Accepted Contract Amount per day of delay per Contract Milestone, subject to max 5% for the project"                                                                                                                                    | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                       |
| 26 | Section-X; Contract Forms; Performance Security; Page 309 of 319<br>Section-X; Contract Forms; Performance Security; Page 310 of 319<br>Section-X; Contract Forms; Performance Security; Page 311 of 319<br>Section-X; Contract Forms; Performance Security; Page 313 of 319 | It is requested to add this NWC clause at the end of Bank Guarantee Form: "Notwithstanding anything contained herein: i. Our liability under this Bank Guarantee shall not exceed _____ .ii. This Bank Guarantee shall be valid up to _____ .iii. We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only and only if Employer serve upon Bank a written claim or demand on or before _____ (@) _____." | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                       |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                                                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                                                                                                         |
|----|--------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 27 | General                                                                                                                                    | <p>It is requested to confirm the present status of following</p> <ol style="list-style-type: none"> <li>1. Forest Clearance</li> <li>2. Environmental Clearance</li> <li>3. Land Acquisition</li> <li>4. Rehabilitation &amp; Resettlement Status</li> <li>5. Any other (like defense etc.)</li> </ol> <p>We construe that all the above approvals shall be obtained by the Employer prior to the Effective Date and any delays in the same shall entitle the Contractor for extension of time and Cost compensation.</p> <p>Request to kindly confirm.</p> | <p>All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation &amp; Resettlement has been completed for the lands identified for the work under the Package.</p>                                                           |
| 28 | Annexure-4; Bill of Quantities; A9.18; Page 10 of 26                                                                                       | The Quantity for slush grout seems to be abnormally high. Request to kindly review.                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Unit of Measurement for the Line Item A9.18 Slush Grout under Annexure 4 Bill of Quantities (Page 10 of 26) is hereby changed to "kg"                                                                                                                                                                                              |
| 29 | Section-IX; Particular Conditions; Cl 1.1.27; Page 229 of 319                                                                              | It is requested to reduce the Defects Notification Period to 12 Months.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                  |
| 30 | Section-IX; Particular Conditions; Cl 8.8; Page 230 of 31                                                                                  | It is requested to reduce the delay damages to 5% of Contract Price                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                  |
| 31 | <p>Section-IX; Particular Conditions; Cl 14.7b (i); Page 230 of 319</p> <p>Section-IX; Particular Conditions; Cl 14.7; Page 278 of 319</p> | <p>The timeline is different in both the mentioned clauses, i.e., 42 days &amp; 56 days.</p> <p>It is requested to replace the clause as follows: "Employer shall release 80% of IPC within 7 days after receiving the Certification from the Engineer and remaining 20% of IPC within 28 days after receiving the Certification from the Engineer."</p>                                                                                                                                                                                                     | <p>Clause 14.7b(i) under Section IX-Particular Conditions Part A Contract Data is hereby amended as follows:</p> <p>"75% of the IPC within 7 days after the Engineer receives the Statement and supporting documents and the remaining 25% within 56 days after the Engineer receives the Statement and supporting documents."</p> |
| 32 | Section-IX; Particular Conditions; Cl 1.5; Page 235 of 319                                                                                 | It is requested to change the order as follows:“(a) the Contract Agreement;(b) the Minutes of Negotiation, if any;(c) the Letter of Acceptance;(d) the amendments and clarifications (if any)(e) Letter of Tender;(f) the Particular                                                                                                                                                                                                                                                                                                                         | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Addendum and Clarification                                                                                                                                                                                                                         |
|----|---------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                               | Conditions Part A - Contract Data;(g) the Particular Conditions Part B - Special Provisions(h) these General Conditions;(i) the Bill of Quantities;(j) the Technical Specifications;(k) the Tender Drawings;(l) the Information for Bidders;(m) the Particular Conditions Part C- Fraud and Corruption;(n) the Particular Conditions Part D- Environmental and Social (ES) Metrics for Progress Reports;(o) Particular Conditions- Part E- Sexual Exploitation and Abuse (SEA) and/or Sexual Harassment Performance Declaration for Subcontractors;” |                                                                                                                                                                                                                                                    |
| 33 | Section-IX; Particular Conditions; Cl 4.20; Page 252 of 319   | It is requested to modify the highlighted clause as follows:<br>“the Contractor shall bring each hindrance to the notice of the Engineer not later than 14 days of the occurrence of the hindrance,”                                                                                                                                                                                                                                                                                                                                                 | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                  |
| 34 | Section-IX; Particular Conditions; Cl 8.1; Page 267 of 319    | It is requested to give a Notice to the Contractor stating the Commencement Date, not less than 14 days before the Commencement Date. And the Commencement Date shall be within 42 days after the Contractor receives the Letter of Acceptance.                                                                                                                                                                                                                                                                                                      | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                  |
| 35 | Section-IX; Particular Conditions; Cl 21.6; Page 286 of 319   | It is requested to provide the Dispute resolution method after the Arbitration procedures (if any, fails) and also provide the Jurisdiction for Dispute resolution (if any means, by Courts).                                                                                                                                                                                                                                                                                                                                                        | If arbitration fails, the next step is formal judicial resolution where the court will discontinue the arbitral proceedings and continue its own hearing of the dispute. Jurisdiction for recourse against awards rests with the courts of Bhutan. |
| 36 | Section-IX; Particular Conditions; Cl 21.6; Page 286 of 319   | It is requested that Arbitration shall be as per ICC Rules of Arbitration. There shall be three Arbitrators. Each arbitrator shall appoint one arbitrator and the appointed two arbitrators shall appoint the third (presiding) arbitrator. The seat shall be at Singapore.                                                                                                                                                                                                                                                                          | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                  |
| 37 | Section-IX; Particular Conditions; Cl 1.1.19; Page 233 of 319 | It is requested to reinstate the FIDIC clause.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                  | Clarifications Sought/Suggestions                                                                                                                                                                                         | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                               |
|----|-----------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 38 | Section-IX; Particular Conditions; Cl 5.1; Page 257 of 319                  | It is requested that nothing in this Clause shall affect any rights and remedies of the Contractor against such Subcontractors which have accrued due to the Subcontractor's defaults committed prior to such assignment. | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 39 | Section-IX; Particular Conditions; Cl 8.5; Page 267 of 319                  | It is requested to delete the mentioned clause.                                                                                                                                                                           | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 40 | Section-IX; Particular Conditions; Cl 13.7; Page 269 of 319                 | It is requested that the contractor shall be entitled to price variation as per the formula provided in clause 13.7 for the period of any extension of time granted pursuant to Sub-Clause 8.5                            | Provisions of the Bidding Document shall prevail, i.e., the contractor shall be entitled to price variation as per the formula provided in Clause 13.7 for the period of any extension of time granted pursuant to Sub-Clause 8.5.                                                                                                                                                                       |
| 41 | Section-IX; Particular Conditions; Cl 14.8; Page 279 of 319                 | It is requested to reinstate the FIDIC clause.                                                                                                                                                                            | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 42 | Section-IX; Particular Conditions; Cl 16.1; Page 280 of 319                 | It is requested to reinstate the FIDIC clause.                                                                                                                                                                            | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 43 | Section-IX; Particular Conditions; Cl 16.2.2; Page 280 of 319               | It is requested to reinstate the FIDIC clause.                                                                                                                                                                            | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 44 | Section-IX; Particular Conditions; Cl 21.11; Page 287 of 319                | It is requested to delete the mentioned clause                                                                                                                                                                            | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                        |
| 45 | Section-III; Evaluation and Qualification Criteria; Cl: 1.5; Page 49 of 319 | It is requested to provide the component-wise equipment list envisaged for the project. The same will facilitate detailed planning, resource assessment and preparation of the construction methodology.                  | Minimum Equipment list has been provided under Section-VII Works' Requirement-Key Equipment and Machineries. Further, as per the requirement under Section IV-Bidding Forms, Form EQU: Contractor's Equipment (Page 78 of 319), the bidder has to submit a progressive Equipment and Machineries Deployment Schedule on a quarterly basis aligned with the Proposed Construction Schedule & work fronts. |
| 46 | Section-VII; Work's Requirement; Cl: 9.1.3; Page 158 of 319                 | It is requested to provide a Layout Drawing showing the location of all boreholes/drilled holes aligned with the project component. Additionally, it is requested to provide the coordinates of the drill holes           | Available GBR and GDR shared as Annexure: DCP-I(b)                                                                                                                                                                                                                                                                                                                                                       |
| 47 | Section-VII; Work's Requirement; Cl: 9.1.3; Page 158 of 319                 | It is requested to provide the Complete exploration data for all drill holes, covering different depths of exploration, including:1. Field                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                          |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                     | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                               |
|----|----------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                | borehole / drill hole logs2. Structural features (joints, shears, faults, crushed zones)3. Weathering classification4. Core box photographs for the full depth of all drill holes, clearly tagged with Borehole ID and Depth Intervals.                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                          |
| 48 | Section-VII; Work's Requirement; Cl: 9.1.3; Page 176 of 319    | It is requested to provide detailed Geophysical survey reports such as Electrical resistivity test and Seismic refraction test.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                          |
| 49 | Annexure 4; BOQ                                                | It is observed that the BOQ provides consolidated quantities for Surface Works and Underground Works. For clear understanding, verification, and construction planning, it is requested to provide component-wise quantities of Surface Works and Underground Works separately.                                                                                                                                                                                                                                                                                                                                                                            | The quantities for Surface and Underground works have already been provided in the BoQ. That is considered to be sufficient information for bidding. The bidder may see the tender drawings in consonance.                                                                                                                                                                               |
| 50 | Annexure 5.1; Work's Requirement; Page 1 of 1                  | It is requested to provide below details:<br>1. AutoCAD file of infrastructure facility area for better understanding and evaluation of distance and capacity of Muck disposal/Quarry sites.<br>2. Drawings of various Infrastructure components.<br>3. KML file for the same                                                                                                                                                                                                                                                                                                                                                                              | KMZ file shared as Annexure DCP-I(a) along with the layout of infrastructure components.                                                                                                                                                                                                                                                                                                 |
| 51 | Annexure 6; Technical Specifications; Cl: B.23; Page 722 of 74 | It is requested to provide the details of the existing road network for the project, including the following:<br>1. ROW, Carriageway Width, Drain, Type of Road.<br>2. Locations, specifications, i.e. loading condition and details of culverts and bridges.<br>3. AutoCAD drawings of the road network layout (Existing & Proposed)<br>4. Contour survey in AutoCAD format for planning of road and cross-structures i.e., culverts and bridges (if any).<br>5. Kindly provide the KML file of the same. Additionally, it is requested to confirm whether the access road to the work site will be available from the commencement of the works (Day 0). | Refer Information for Bidders under Section VII- Work's Requirement. Request to visit the site as mandated by the Section II-Bid Data Sheet, Sub-Clause ITB 7.2. Access Roads to the work site will be available from the commencement of the works except for the connecting road between Adit 3 and 4 are expected to be completed within first one year of award of the main package. |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Addendum and Clarification                                                                                                                                                                                                                                                                                                                       |
|----|----------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 52 | Annexure 7; Drawings; Page 7 of 69                                         | In the mentioned drawing, RCC Carapace and RCC block are shown but the quantity of the same is not reflected in BOQ sheet. Request to clarify.                                                                                                                                                                                                                                                                                                                                                      | The quantity is included under A9 Concrete                                                                                                                                                                                                                                                                                                       |
| 53 | Annexure 7; Drawings; Page 7 of 69<br>Annexure 7; Drawings; Page 7 of 69   | It is requested to provide detailed fixing systems, anchorage trench, overlaps/jointing details.                                                                                                                                                                                                                                                                                                                                                                                                    | These are to be executed as per relevant international standards which are mentioned in the TS Section 1.3                                                                                                                                                                                                                                       |
| 54 | Annexure 7; Drawings; Page 8 of 69                                         | In the mentioned drawing, RCC Plinth Beam is shown but the quantity of the same is not reflected in BOQ sheet. Request to clarify.                                                                                                                                                                                                                                                                                                                                                                  | The quantity is included under A9 Concrete                                                                                                                                                                                                                                                                                                       |
| 55 | Annexure 7; Drawings; Page 21 of 69<br>Annexure 7; Drawings; Page 22 of 69 | In Section E, F Sufficient Details of Rock Support bolts are not provided. It is requested to provide the same. Additionally, it is requested to provide the Lining thickness of the Adit.                                                                                                                                                                                                                                                                                                          | Available Annexure 7 drawings to be referred. The details for each type of support class are given in the adjacent window on the drawings. As per the tender design, the steel sets are to be embedded in shotcrete and the thickness of shotcrete is mentioned to be > 10 cm. The concrete lining is only provided at the invert. (See page 23) |
| 56 | Annexure 7; Drawings; Page 23 of 69<br>Annexure 7; Drawings; Page 24 of 69 | The cross sections do not clearly specify the type of support system; only general details are provided. It is requested to indicate the specific support type applicable.                                                                                                                                                                                                                                                                                                                          | Please refer the Notes on this drawing. Surface excavation support details are given in a separate drawing referred to herein.                                                                                                                                                                                                                   |
| 57 | Annexure 7; Drawings; Page 34 of 69<br>Annexure 7; Drawings; Page 35 of 69 | It is observed in the provided dam excavation drawings; no benches were considered along the bank excavation. It is requested to kindly clarify if the dam excavation profile will be provided with benches or not as approach through benches will be required to access the proposed inspection galleries at different levels. Also, introduction of these benches will lead to additional excavation quantities, and if yes, whether the same quantity is considered in the provided BOQ or not. | The stripping limits, elevations, and bench details indicated in Instrumentation Drawing No. DHPP-CD-DAM-2026-122/750-DAM-D-SP-022-B may be referred to.                                                                                                                                                                                         |
| 58 | Annexure 7; Drawings; Page 42 of 69                                        | In the mentioned drawing, Pendulum Shaft typical section is provided. It is requested to provide the height and depth of                                                                                                                                                                                                                                                                                                                                                                            | Details will be only available during the detailed design phase.                                                                                                                                                                                                                                                                                 |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                                | Clarifications Sought/Suggestions                                                                                                                                                                                                                                    | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|----|-----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                           | the shaft to be excavated in the dam Foundation in tender drawings. Additionally, it is requested to provide the metal works details such as ladder, etc.                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| 59 | Annexure 7; Drawings; Page 42 of 69<br>Annexure 4; Bill of Quantities; Page 14 of 26                      | In Tender Drawing & BOQ, Inverted and Direct Pendulum are mentioned. It is requested to provide the location of those structures and relevant supporting details regarding the same, as they are not provided in the Tender Drawings                                 | These are standard equipment and the details may vary for individual instrument suppliers. The bidders are expected to carry out due -diligence by themselves                                                                                                                                                                                                                                                                                                                                                                                  |
| 60 | DHPP-CD-ADT-2026-103 & DHPP-CD-ADT-2026-104                                                               | In Section D, E, F Proper Details of Pattern Rock bolts not provided. In HRT Final Lining, there is mention of Note-3 in some sections, However, Note 3 is not provided in drawing, Lining thickness is not mentioned. Kindly provide the details.                   | The rock support details are given in the adjacent window of each support class section. Lining thickness is already defined by stating the internal and external radius.                                                                                                                                                                                                                                                                                                                                                                      |
| 61 | DHPP-CD-CD-2026-102 & DHPP-CD-CD-2026-103                                                                 | No detailed fixing system, anchorage trench, overlaps/jointing is provided. Kindly provide the same.                                                                                                                                                                 | Details will be only available during the detailed design phase.                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 62 | Annexure 6; Technical Specifications; Section: B.22; 22.11.1, 22.11.2 and 22.11.3.2; Page 664, 665 of 744 | Total quantity of spillway stoplogs is mentioned as 2 numbers in clause 22.11.1 and 22.11.3.2, however same is mentioned as 1 number in clause 22.11.1. Requested to reconfirm the final requirement of quantity of stoplogs.                                        | The number of stoplogs set has been confirmed as 1. The text (Particular Technical Specification (PTS) and BoQ) have been modified accordingly. Amended BoQ and PTS is attached as Annexure DCP-I(h) and DCP-I(i) respectively.                                                                                                                                                                                                                                                                                                                |
| 63 | Annexure 6; Technical Specifications; Section: B.22; 22.12.11; Page 680 of 744                            | As per IS:4622 and IS:4623, Permissible leakage for fixed wheel and radial gate is: 5l/min per meter of seal length for low and medium head gates. 10l/min per meter of seal length for high head gates. Request to confirm regarding final values to be considered. | The maximum permissible leakage rate to be adopted for the design of the gates shall be 1.2 L/min per metre of seal length, as specified in the Technical Specification. The values indicated in IS 4622 and IS 4623 represent general permissible leakage limits under those standards. However, the specified leakage requirement of 1.2 L/min per metre of seal length shall prevail, as it constitutes the project-specific performance requirement and is more stringent than the corresponding values given in the referenced standards. |
| 64 | Annexure 6; Technical Specifications; Section: B.22; 22.12.11; Page 680 of 744                            | As per IS:4622, Permissible leakage for fixed wheel gate is: 5l/min per meter of seal length for low and medium head gates. 10l/min per meter of seal length for high head gates. Request to confirm regarding final values to be considered.                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                               | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                               | Addendum and Clarification                                                                                                                                                                                                                                                                                                  |
|----|----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 65 | Annexure 6; Technical Specifications; Section: B.22; 22.13.9; Page 689 of 744                            | As per IS:4622 and IS:9349, Permissible leakage for fixed wheel and Sliding gate is: 5l/min per meter of seal length for low and medium head gates. 10l/min per meter of seal length for high head gates. Requested to confirm regarding final values to be considered.                                                                                                                                         |                                                                                                                                                                                                                                                                                                                             |
| 66 | Annexure 6; Technical Specifications; Section: B.24; 24.2.1(3) & 24.2.3.1; 22.7.8.3; Page 728-744 of 744 | The specification states that "The LED fittings may be proposed" but does not mandate them. Please confirm whether LED luminaires are mandatory or if conventional types are also acceptable. Additionally, Request to confirm whether there are specific requirements for efficacy, CRI, or colour temperature for the fittings. As per reference clause 22.7.8.3, CRI≥80; CCT<4000K may be considered or not. | Use of LED fittings is mandatory and the Contractor shall ensure that the visual requirements of each area to ensure optimal illuminance is achieved.                                                                                                                                                                       |
| 67 | Annexure 6; Technical Specifications; Section: B.24; 24.2.4(4) & 24.2.5(1) ; Page 728-744 of 744         | Emergency lighting is required in the control room, but the backup duration is not specified in B.24. Please clarify the minimum autonomy and required illumination level during emergency mode.                                                                                                                                                                                                                | The system will meet or exceed NFPA 101 requirements, ensuring a minimum operation time of 90 minutes, with a project-specific target of two hours to maintain consistency with the UPS battery life. Emergency lighting intensities are summarized in the table provided under section 22.7.8.3 (Technical Specification). |
| 68 | Annexure 6; Technical Specifications; Section: B.24; 24.2.7(1) & 24.2.21; Page 728-744 of 744            | Cables are specified to be at least 600V/1000V grade. Please confirm if standard 1100V grade is acceptable. Furthermore, equipment must be type tested as per "relevant IEC standards & Bhutanese/Indian Standards". Please provide a definitive list of applicable standards for lighting equipment, cables, and distribution boards.                                                                          | 1100V grade is acceptable. Relevant IS standards and latest Specification for Electrical Materials & Works published by Ministry of Infrastructure & Work for Bhutan Schedule of Rates, RGoB.                                                                                                                               |
| 69 | Annexure 6; Technical Specifications; Section: B.24; 24.2.23; Page 728-744 of 744                        | The specification requires field testing for insulation resistance but does not state the minimum acceptable megohm values. Please provide the acceptance criteria                                                                                                                                                                                                                                              | Refer to IEC or any applicable Bhutanese/Indian Standards                                                                                                                                                                                                                                                                   |
| 70 | Annexure 6; Technical Specifications; Section: B.24;                                                     | The elevator shall conform to "relevant IS codes". Please confirm the specific IS standard IS 14665 (Part 1) :2000 (Superseding IS 3534: 1979) to be                                                                                                                                                                                                                                                            | The sizing of the well shall be available in the detailed design stage and latest relevant IS Code shall be followed.                                                                                                                                                                                                       |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                        | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                               | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                  |
|----|---------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    | 24.3.1(1) & 24.3.6(1) ; Page 728-744 of 744                                                       | followed. Additionally, the Contractor must submit well dimensions. Since as per the above std the well size for elevator of 8 passengers as 1.9mX1.9m so, please confirm whether the bidder can consider the same.                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                             |
| 71 | Annexure 6; Technical Specifications; Section: B.24; 24.3.2(1) & 24.3.10; Page 728-744 of 744     | The specification requires a "modern aesthetically pleasing appearance". Please provide specific finish, material, and colour requirements for the elevator car. Also, the supply must include "One complete motor of each type and size" as spare parts. Please clarify if this refers only to the hoist motor or includes door operator and auxiliary motors. | Finish shall be decided during construction phase on review of the proposal of the Contractor. It shall also include door operator and auxiliary motors.                                                                                                                                                                                                                    |
| 72 | Annexure 6; Technical Specifications; Section: B.24; 24.4.3(1) ; Page 728-744 of 744              | The required equivalent resistance of the whole earth electrode and main earth collector is $\leq 1 \Omega$ . Please confirm if this value must be met under all soil moisture conditions (dry and wet seasons) and specify the reference standard for measurement.                                                                                             | The specified earth resistance of $\leq 1 \Omega$ should be confirmed with respect to the design basis, which are generally the most unfavourable seasonal soil conditions (i.e., dry season). The earth resistance should be measured in accordance with IEEE Std 81."                                                                                                     |
| 73 | Annexure 6; Technical Specifications; Section: B.24; 24.4.3(1) & 24.4.6(f) ; Page 728-744 of 744  | Conductors are to be dimensioned for "carrying earth fault current... for at least one second". Please provide the design earth fault current value for the dam area to enable proper sizing.                                                                                                                                                                   | To be defined by the Contractor.                                                                                                                                                                                                                                                                                                                                            |
| 74 | Annexure 6; Technical Specifications; Section: B.24; 24.4.10(1) & 24.4.6(c) ; Page 728-744 of 744 | The specification references "ANSI/IEEE Std 80-1986". Request to confirm whether the latest version (IEEE Std 80-2013) is acceptable                                                                                                                                                                                                                            | Acceptable.                                                                                                                                                                                                                                                                                                                                                                 |
| 75 | Annexure 6; Technical Specifications; Section: B.24; 24.5; Page 728-744 of 744                    | The specification states: "In each of these pits, three (3) operational pumps and one (1) in stand-by to the others and one bilge pump shall be provided". Please definitively confirm the total quantity required per pit is 5 (3 operational, 1 standby, 1 bilge).                                                                                            | Please refer to the Tender drawings and the Technical Specifications. The sump pit and associated pumping system shown in the current tender shall be considered indicative and subject to further refinement. The final number of pumps, redundancy requirements, operating duties, and hydraulic sizing shall be determined during the subsequent detailed design phase." |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                      | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                      |
|----|-------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 76 | Annexure 6; Technical Specifications; Section: B.24; 24.5.3; Page 728-744 of 744                | The specification requires the provision of valves for de-aeration or drainage "in case of necessity". Please confirm if de-aeration valves are mandatory at all high points of the piping system or if their inclusion is at the Contractor's discretion.                                                                                            | Contractor's discretion. However, cost to be factored in main BoQ line items, if required.                                                                                                                                                                                                                                                                                      |
| 77 | Annexure 6; Technical Specifications; Section: B.24; 24.5.8; Page 728-744 of 744                | The list of controls and indications includes "Other required indications and control and current/voltage measurement". Please provide a complete and definitive list of all required indications, controls, and measurements to enable accurate panel design and costing.                                                                            | These items are discretionary and depend on the final design and functionality of the drainage systems.                                                                                                                                                                                                                                                                         |
| 78 | Annexure 6; Technical Specifications; Section: B.24; 24.5.13 & 24.5.10; Page 728-744 of 744     | A test pressure of 15 kg/cm <sup>2</sup> is specified. Please confirm if this applies to the entire piping system or specific sections. Additionally, please confirm if the test duration is strictly 24 hours without pressure loss. Are field performance tests (e.g., pump capacity, head) required at site, and what are the acceptance criteria? | It applies to the entire piping system                                                                                                                                                                                                                                                                                                                                          |
| 79 | Annexure 6; Technical Specifications; Section: B.24; B.24 & B.22; Page 728-744 of 744           | Both specifications reference "Bhutanese/Indian Standards" and "IEC" throughout. Please provide a consolidated list of all applicable standards with their versions to be followed for the design, manufacturing, testing, and installation of all E&M equipment.                                                                                     | Please refer Clause 1.3.2 of the TS in this regard. However, wherever necessary specific codes have already been given in the TS.                                                                                                                                                                                                                                               |
| 80 | Annexure 6; Technical Specifications; Section: B.24; B.24 & B.22; Page 728-744 of 744           | Please clearly state if the detailed electrical specifications in Section B.22 (control panels, motors, cables, earthing) apply in full to the equipment defined under B.24 (lighting, elevator, grounding, drainage pumps).                                                                                                                          | The bidder must adhere to the detailed requirements for control panels, motors, cables, and earthing found in Section B.22 for the equipment in Section B.24, unless Section B.24 explicitly provides a different, overriding requirement.                                                                                                                                      |
| 81 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.2 vs. B.24.2.5; Page 728-744 of 744 | B.22.7.2 requires local control panels to be IP-65, whereas B.24.2.5 only states "waterproof" for distribution boards, and no IP rating is specified for drainage pump panels. Please confirm the minimum IP rating for each specific panel under                                                                                                     | Local control panels supplied under Section B.22 shall have a minimum enclosure protection rating of IP65, whether installed indoors or outdoors. Lighting distribution boards under Section B.24 shall also have a minimum enclosure protection rating of IP65. Individual terminal panels and local control panels for the drainage water pumping system shall have a minimum |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                             | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|----|-------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                       | B.24 and whether B.22 requirements supersede B.24.                                                                                                                                                                                                                                                                            | protection rating of IP65. Where installed inside drainage galleries, pump pits or other locations subject to direct splashing, water jets or particularly severe moisture conditions, the minimum rating shall be IP66. Central drainage control and indication panels installed in the dam control building or another dry, environmentally controlled electrical room may be rated IP54 minimum, unless the actual installation conditions require a higher rating. The submersible pump motors shall remain IP68, as already specified in Section B.24."                                                                                   |
| 82 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.5 vs. B.24.5.2; Page 728-744 of 744       | B.22.7.5.2 specifies service factors and requires direct-on-line starting with a maximum starting current of 5 times rated. Request to confirm whether these requirements strictly apply to the submersible drainage pump motors (IP68) under B.24. If not, please specify the applicable motor requirements for those pumps. | Direct-on-line starting may be adopted only where supported by the electrical-system calculations and the motor manufacturer. The Contractor shall demonstrate that: 1. the resulting starting current and voltage drop are acceptable for the supplying transformer, cables, switchgear and other connected loads; 2. the motor develops sufficient accelerating torque throughout the starting period; 3. the starting duration and thermal duty remain within the motor limits; and 4. no unacceptable hydraulic or mechanical transient is produced. The actual starting current shall be based on the selected motor and starting method. |
| 83 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.8.1; Page 728-744 of 744                  | B.22.7.8.1 mandates a minimum power cable size of 16 mm <sup>2</sup> and control cable of 1.5 mm <sup>2</sup> . Request to confirm whether this 16 mm <sup>2</sup> minimum power cable requirement apply to all small power and lighting circuits under B.24. If not, please clarify the exceptions.                          | 16mm <sup>2</sup> is a minimum cross-section for power feeders associated with the hydromechanical equipment covered by B.22, unless cable-sizing calculations require a larger section.<br><br>Section B.24 expressly requires cable and conduit sizing calculations for lighting installations.                                                                                                                                                                                                                                                                                                                                              |
| 84 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.8.3 vs. B.24.2.1(3) ; Page 728-744 of 744 | B.22.7.8.3 specifies 538 Lux for the control room, compared to B.24.2.1(3) which specifies 500 Lux. Request to confirm which set of illumination levels shall govern the design of the lighting systems under B.24.                                                                                                           | The illumination levels specified in Section B.24 shall govern the design of the lighting systems included within the scope of Section B.24. However, where a corresponding requirement in another section is more stringent, the higher illumination level shall apply unless otherwise stated.                                                                                                                                                                                                                                                                                                                                               |
| 85 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.7; Page 728-744 of 744                    | B.22.7.7 states the Owner will provide a 33/0.415 kV transformer, and the Contractor shall arrange the LT distribution board, capacitor bank, cables,                                                                                                                                                                         | The additional scope of tapping of line from 33 kV trunk line, if required along with transformer and LV supply will be in contractor's scope upon approval from the Employer. Locations of transformer has been shown during the site visit.                                                                                                                                                                                                                                                                                                                                                                                                  |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause                                                                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                                                               | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                       |
|----|-------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|    |                                                                                                       | etc. Please provide the maximum distance from the transformer to the first distribution board.                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| 86 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.8.3 vs. B.24.2.1(3) ; Page 728-744 of 744 | B.22.7.8.3 requires emergency lighting for a minimum of 90 minutes. Request to confirm whether this requirement is applicable to the emergency lighting specified in B.24 for the control room and galleries?                                                                   | Yes. The emergency-lighting autonomy requirement specified in Section B.22 shall also apply to the emergency-lighting systems supplied under Section B.24.                                                                                                                                                                                                                                                                                       |
| 87 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.6.4; Page 728-744 of 744                  | The specification for protection relays is detailed but does not mention an approved manufacturer list. Request to confirm in case there are any preferred makes or restrictions on relay types that must be adhered to for costing purposes?                                   | Protection relays shall be numerical or static relays from an internationally recognised manufacturer with proven references in comparable installations. The proposed manufacturer and relay types shall be subject to the Engineer's approval. No mandatory manufacturer list applies at tender stage; however, relay platforms shall be standardised throughout the installation, and obsolete or unsupported products shall not be accepted. |
| 88 | Annexure 6; Technical Specifications; Section: B.24; B.22.7.2 & B.22.7.8.2; Page 728-744 of 744       | Colour codes for wiring and mimic diagrams are specified. Please confirm if these are strictly mandatory and whether any deviations are acceptable with the Engineer's approval. Request to confirm whether any requirement is there for local language labels on these panels. | Any changes of the design of any part of the Works, which may become necessary after signing the Contract, have to be submitted in writing to the Engineer for approval, being sufficiently substantiated and justified.<br><br>Latest specification for electrical materials & works published by Ministry of Infrastructure & Work for Bhutan Schedule of Rates, RGoB to be followed on colour coding of wires.                                |
| 89 | Annexure 6; Technical Specifications; Section: B.24; B.22.8 & B.22.9; Page 728-744 of 744             | B.22.8 and B.22.9 impose detailed requirements for packing, marking, storage, and testing. Please confirm that these apply equally to all E&M equipment under B.24, and request to clarify if specific test procedures must be performed at an accredited third-party lab.      | No, it does not apply equally to all E&M equipment. Each section has its own dedicated testing chapter.                                                                                                                                                                                                                                                                                                                                          |
| 90 | General                                                                                               | Kindly confirm Interfaces with DCP-II / DCP-III packages.                                                                                                                                                                                                                       | All work fronts for DCP-I, DCP-II and DCP-III are independent, other than the facilities mentioned in the Bidding Document.                                                                                                                                                                                                                                                                                                                      |
| 91 | General                                                                                               | Kindly provide Face advance assumptions to be used Per rock class (Type A–F). It is required for realistic scheduling.                                                                                                                                                          | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and                                                                                                                                                                                                                                                                             |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN | RFB Clause | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Addendum and Clarification                                                                                             |
|----|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|
|    |            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | demonstrate the completion of DCP-I within the stipulated contract period.                                             |
| 92 | General    | <p>Kindly clarify whether any adjustment should be considered for the monsoon period while determining the excavation duration and planning, as excavation progress is expected to be significantly impacted during the monsoon season.</p> <p>Additionally, please specify if there are any constraints or restrictions related to muck disposal/dumping activities that could affect mucking cycle times and overall productivity.</p>                                                                                                                                                                                                                       | The Bidder is required to submit a detailed Construction Schedule adopting the available data in the Bidding Document. |
| 93 | General    | As the construction methodology is not specified in the tender documents, we understand that the bidder shall prepare and submit the Method Report based on its own proposed construction methodology and planning. Kindly confirm.                                                                                                                                                                                                                                                                                                                                                                                                                            | Yes                                                                                                                    |
| 94 | General    | Kindly furnish survey contour data of the project site, clearly depicting all project components along with the associated road network.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)                                                 |
| 95 | General    | <p>It is requested to furnish rock mass class distribution percentage for project components to enable accurate estimation of support requirements and effective excavation planning. The components for which such distribution is required are: 1. Head race tunnel (HRT) from CH 129 to CH 2485 m1. Head race tunnel (HRT) from CH 129 to CH 2485 m2. Adit No. 1 to HRT3. Connection tunnel to Dam Top4. Feeder tunnel5. Dam6. Cofferdam7. Intake</p> <p>Additionally, it is requested to provide chainage-wise rock mass classification (based on RMR) for tunnel components, as same is required to evaluate the anticipated progress for each class.</p> | Available GBR and GDR shared as Annexure: DCP-I(b)                                                                     |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                 | Clarifications Sought/Suggestions                                                                                                                                                  | Addendum and Clarification                                                                                                                                                                                                                                    |
|-----|----------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 96  | General                                                                    | Kindly provide detailed geological data, including geological mapping records and drawings illustrating the complete geological formations/overburden along all project components |                                                                                                                                                                                                                                                               |
| 97  | General                                                                    | Kindly provide, project schedule, as the same is required for effective planning and sequencing of construction activities.                                                        | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period.               |
| 98  | General                                                                    | It is requested to provide the AUTOCAD Files of the Provided Drawings in the Tender Document.                                                                                      | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)                                                                                                                                                                                        |
| 99  | General                                                                    | It is requested to provide the current status of land acquisition of the project.<br>1. Government Land<br>2. Forest Land<br>3. Private Land                                       | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation & Resettlement has been completed for the lands identified for the work under the Package. |
| 100 | General                                                                    | It is requested to provide the DPR for better assessment of the project                                                                                                            | All the relevant information has been provided in Bidding Documents.                                                                                                                                                                                          |
| 101 | General                                                                    | Kindly provide the likely date of award of contract to plan for the resources according to the start date.                                                                         | October 2026                                                                                                                                                                                                                                                  |
| 102 | Clause 22.2.3 - Material Standard(GTS)                                     | As per the practice and guidelines of Indian Standards the skin plate for submerged Top Sealing Radial Gate is recommended as stainless steel. Please clarify and confirm.         | Please refer to the technical specifications where it is stated "The side, the top and the bottom sealing plates will be stainless steel. Each gate will be operated by two oil operated servo motors. " (section 22.11.3.1)                                  |
| 103 | Clause 22.11.3.1 - Spillway Radial Gates(PTS)                              | Material of Skin Plate is not specified.                                                                                                                                           | Please refer to the technical specifications where it is stated "The side, the top and the bottom sealing plates will be stainless steel. Each gate will be operated by two oil operated servo motors. " (section 22.11.3.1)                                  |
| 104 | Drg. No. DHPP-HM-DAM-2024-103 - Spillway Radial Gate - General Arrangement | The Trunnion Girders for Radial Gates are of concrete with prestressed anchors. We presume that these trunnion girders shall be in the Scope of Civil Works. Please confirm.       | Trunnion girders are included in the DCP-I Scope                                                                                                                                                                                                              |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                        | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                           |
|-----|----------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 105 | Drg. No. DHPP-HM-DAM-2024-103 - Spillway Radial Gate - General Arrangement | Please clarify whether these Radial Gates can also be designed with 2 nos, Trunnion Assemblies which shall ease the alignment during erection since co-centricity of 2 Nos. trunnions shall be easier to maintain than 4 nos. Trunnions.                                                                                                                                                                                                                                 | The proposed arrangement with 2 No. trunnion assemblies is acceptable, provided that the design complies with all the specified functional, structural, operational, and safety requirements                                                                                                                                                                         |
| 106 | Annexure -4- Bill of Quantities- Part 2                                    | In the BoQ, the pipes for environment release should be included. Further, there is no valve to control the flow. Please clarify and confirm.                                                                                                                                                                                                                                                                                                                            | The Environmental Flow Release System is included and paid on a lump-sum basis under Item A22.4, as a complete and operational system including all accessories and ancillary equipment, in accordance with the Technical Specifications.                                                                                                                            |
| 107 | Bill of Quantities                                                         | Please provide soft copy in Excel Format.                                                                                                                                                                                                                                                                                                                                                                                                                                | The Bidder to use the available Bill of Quantities                                                                                                                                                                                                                                                                                                                   |
| 108 | Drawings                                                                   | Please provide these drawings in Auto-CAD format also.                                                                                                                                                                                                                                                                                                                                                                                                                   | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)                                                                                                                                                                                                                                                                                               |
| 109 | Drawing No. DHPP-HM-INTAKE-2026-109 & 110-Intake Trash Racks               | In Section-3 and Detail "B" The horizontal beam (6100mm span) is shown of steel. However in key section it seems of concrete. In our opinion the horizontal girder should be of concrete for better flow conditions and low head loss. Kindly confirm and clarify.                                                                                                                                                                                                       | Please refer to tender specifications where structural steel is specified.                                                                                                                                                                                                                                                                                           |
| 110 | Drawing No. DHPP-HM-INTAKE-2026-109                                        | The Spacing between bar of the Trash Rack Panel is shown in the drawing as 75mm c/c whereas in the technical specification this is mentioned as 75mm as clear spacing. Kindly confirm the c/c spacing the bars. Also, please clarify the meaning of <b>"to be confirmed by the Contractor during L1 design."</b>                                                                                                                                                         | The spacing between the bars will depend strictly on the turbine rotor that will be installed and will be specified by the EM contractor. This is the meaning of "to be confirmed by the Contractor during L1 design." As for the 75 mm indicated, these figures are to be considered purely indicative and preliminary, since the rotor has not yet been finalized. |
| 111 | Clause 22.14.2 of Main Works Section B-32 page 80 of 110                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                      |
| 112 | Section B.22-HSS Equipment- Technical Specification                        | We understand the in terms of Clause 22.1.2 the detailed design which inter alia include design fabrication calculations and shop drawings for HSS equipment shall be carried out by the Main Design Consultant (DC) to be appointed by the employer. Hence weight of HSS equipment should be mentioned in the BoQ in place of sets. However, in terms of clause 22.3.2 manufacturer of HSS equipment have also been assigned the responsibility of detailed fabrication | The Design Consultant (DC) will prepare the detailed design with relevant calculations and all general arrangement drawings. The HSS supplier shall prepare the shop drawings along with bill of quantities.                                                                                                                                                         |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                          | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|--------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                            | and preparation of shop drawings to be approved by Employer.                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 113 | Section B.22-HSS Equipment-Technical Specification                                         | The applicable Indian Standards for Radial Gate and fixed Wheel Vertical Gates are IS:4622 respectively.<br>Kindly include these Indian Standard also in this list                                                                                                                                                                                                                                                         | DIN 19704 already provides adequate and comprehensive design criteria for gates. Introducing standards with different requirements could lead to conflicts. However, relevant IS code meeting the design criteria of the gates may be referred.                                                                                                                                                                                   |
| 114 | Clause No.4.3                                                                              | Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.65 million m3 in any one year in a Dam/Weir/Barrage in the last 20 years in <b>Multiple</b> projects.                                                                                                                                                                                                | Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i) is hereby amended as:<br><br>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m3 in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.<br><br>The Dam height and progress of concreting can be met through two separate projects".                |
| 115 | Section I - Instructions Bidders, Clause 14.8 & Section II- Bid Data Sheet, Clause ITB14.1 | As per Clause 14.8 of the Instruction to Bidders (ITB), all taxes and duties are required to be included in the Price Bid. However, as per Clause 14.8 of the Bid Data sheet, the Bid Price is to be quoted exclusive of Goods and Services (GST) and Import duties. In view of the above discrepancy, we kindly request you to clarify the taxes and duties that are to be considered in the Bid Price                    | Bid Data Sheet shall prevail over Instructions to Bidders, i.e. Bid price to be inclusive of withholding Tax Deducted at Source (TDS) and exclusive of the Goods and Services Tax (GST) and Import Duties. The Bidder shall factor in the applicable withholding Tax Deducted at Source (TDS) in compliance with the Income Tax Act of Bhutan 2025 and Rules on the Income Tax Act of Bhutan 2025.                                |
| 116 | Section II- Bid Data Sheet, ITB 4.1                                                        | Since, hydropower components such as dams, barrages, tunnels, shafts, etc. are also constructed under other infrastructure projects namely water resources projects, road tunnels and railway tunnels wherein the equipment and construction methodologies are largely similar to those employed in hydropower projects. In view of the above, we kindly request you to consider experience from the infrastructure sector | ITB 4.1 under Section-II Bid Data Sheet is hereby amended as "Maximum number of members including the Lead Member in the Joint Venture (JV) shall be 2 (Two). At Least one JV member shall have experience in construction of hydropower project in the Himalayan Region. For construction of head race tunnel, experience in construction of road tunnel, metros, railway tunnels in Himalayan Region shall also be acceptable." |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                                                                           | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                      |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                                                                                      | such as water resources and tunnelling sectors as eligible for qualification.                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| 117 | Section III- Evaluation and Qualification Criteria, Clause 4.1 General Construction Experience and Clause 4.2 Specific Construction & Contract Management Experience | We request you to kindly confirm the cut-off date for determining the 20-year experience period stipulated under the qualification criteria                                                                                                                                                                                                                                                                                                                                      | The cut-off date shall be from the last date of submission of Bid.                                                                                                                                                                                                                                                                                                                                                              |
| 118 | Section III- Evaluation and Qualification Criteria, Clause 4.1 General Construction Experience                                                                       | We understand that the requirement pertaining to Civil General Construction Work Experience may be satisfied through experience in any infrastructure related works. Kindly confirm. Thus interpretation is consistent with the general practice followed in hydroelectric project tenders invited by Central Public Sector Undertakings (PSUs) in India. For your reference, an extract from the tender document of the Kamala Hydroelectric Project is enclosed as Annexure-I. | General Civil Construction Work Experience shall be considered                                                                                                                                                                                                                                                                                                                                                                  |
| 119 | Section III- Evaluation and Qualification Criteria, Clause 4.2 Specific Construction & Contract Management Experience                                                | We understand that the minimum height requirement of 85 m may be satisfied through experience obtained from one project, while the requirement for annual concreting progress of 0.65 million m <sup>3</sup> may be satisfied through experience obtained from another project. Kindly confirm whether our understanding is correct and that these two eligibility criteria can be met independently through separate projects.                                                  | Section III- Evaluation and Qualification Criteria, Sub-Clause 4.2(i) is hereby amended as:<br><br>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m <sup>3</sup> in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.<br><br>The Dam height and progress of concreting can be met through two separate projects". |
| 120 | Section III- Evaluation and Qualification Criteria, Clause 4.2 Specific Construction & Contract Management Experience                                                | As per the general practice followed in dam package tenders for hydroelectric projects invited by CPSUs in India, provisions are included where quantity-based criteria are accepted as an alternative to the dam height requirement. An extract from the Dam Package Tender of the Sawalkot Hydroelectric Project (1856 MW) is attached herewith for your reference as Annexure                                                                                                 | Section III- Evaluation and Qualification Criteria, Sub-Clause 4.2(ii) is hereby amended as: "Successfully achieved excavation for Dam/Barrage/Weir complex for River Diversion of minimum excavation volume of 0.80 million m <sup>3</sup> in any one year in the last 20 years in the single project."                                                                                                                        |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                            |
|-----|-----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                                       | III In view of the above, we kindly request you to consider modifying the eligibility criteria as follows: (i) Dama) Completion of at least one Concrete Dam of minimum height of 85 m; OR b) Completion of total surface excavation of 8,00,000 m <sup>3</sup> and total concreting of 6,40,000 m <sup>3</sup> in one major component of a Water Resources Project (considering 40% of the total excavation and concreting quantities of the dam component). The excavation and concreting quantities may be derived from the same or different Water Resources Project. We trust that the above modification will facilitate broader participation while ensuring that the requisite technical capability and experience requirements are adequately met. We request your kind consideration of the above proposal.                                                 |                                                                                                                                                                                                                                                                                                                                                                                                       |
| 121 | Section III- Evaluation and Qualification Criteria, Clause 4.2 Specific Construction & Contract Management Experience | We understand that the Specific Work Experience for tunnels may be satisfied through tunnelling works executed in any infrastructure project, such as highway tunnels, railway tunnels, or metro tunnels constructed using Drill and Blast Method (DBM) and/ or New Austrian Tunnelling Method (NATM). Kindly confirm. The equipment deployed, construction methodology, tunnelling sequence, ground support systems, and overall execution practices for DBM/NATM tunnels are generally similar across hydroelectric, highway, railway, and metro tunnelling projects. Accordingly, experience gained in such infrastructure tunnelling works provides the requisite technical competence and expertise for the construction of hydroelectric tunnels. Further, this approach is in line with the general practice followed in hydroelectric project tenders invited | Section III- Evaluation and Qualification Criteria, Sub-Clause 4.2(iii) is hereby amended as:<br>"Experience of having excavated an underground tunnel and concrete lining works of at least 1.3 km face length having finished diameter of 7 m or more in the last 20 years in a single project. Underground tunnel shall cover underground hydro/highway/railway/metro/irrigation project tunnels." |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                     | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                               |
|-----|----------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                | by CPSUs in India, wherein tunnelling experience from infrastructure projects is considered for meeting the specific work experience requirements. For your reference, an extract from the tender documents of the Kamal Hydroelectric Project is enclosed as Annexure-III                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                          |
| 122 | Sec. VII, Work's requirement, Cl. 6.2.2.1 & 6.2.2.2            | Kindly confirm the following: 1. The current status of these residential facilities. 2. Date by which these facilities will be handed over. 3. Upon completion of the work, who will have ownership of these facilities?                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Residential Facilities are under construction and will be handed over in line with the provisions mentioned in the Bidding Document. The contractor shall have the ownership of Residential facilities.                                                                                                                                                                  |
| 123 | Section IX- Particular Conditions, Part A - Contract Data      | <p>As per the general practice in hydropower project tenders invited by CPSUs in India, the works are typically executed in accordance with the FIDIC Conditions of Contract (Red Book). Under this framework, construction is carried out based on the design and drawings provided by the Employer, and the Defects Notification Period (DNP) is generally stipulated as 12 months.</p> <p>In view of the above, we kindly request you to review the Defects Notification Period specified in the tender and may please be reduced the same to 12 months.</p> <p>An extract from the tender document of the Kamala Hydroelectric Project is enclosed herewith for your ready reference as Annexure-VI.</p> | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                        |
| 124 | Section IX- Particular Conditions, Part B - Special Provisions | 1. We understand that the equipment listed under Clause 2.6 will be handed over to the Contractor at the Site on the Date of Commencement of work. Kindly confirm the same. 2. Please provide the recovery schedule. 3. We request you to kindly provide year of manufacturer, specifications of the equipment, including make, capacity, etc.                                                                                                                                                                                                                                                                                                                                                               | The equipment will be handed over at the site within the mobilization period and the cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)). The Details of equipment has been provided as Annexure DCP-I(d). |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                      | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                          |
|-----|---------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 125 | Section IX- Particular Conditions, Part B - Special Provisions, sub clause 4.30 | As this is an 'Item Rate Contract' wherein monthly payment will be released by the Client as per the work done. Therefore, keeping amount equivalent to three months of the equated monthly Accepted Contract Amount in the Escrow account will impact the cash flow of the project and also may hamper the project progress. Therefore, we request you to kindly delete this requirement.                                                                                                                                                                                        | Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as" "The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in an amount equivalent to one month of the equated monthly Accepted Contract Amount."                             |
| 126 | Section IX- Particular Conditions, Part B - Special Provisions, sub clause 14.1 | Kindly provide a copy of the Tax Guidelines applicable to the Dorjilung Hydroelectric Power Project for our reference.                                                                                                                                                                                                                                                                                                                                                                                                                                                            | The Custom Duty and GST Exemptions certificate shall be issued or reimbursed for imports of materials and equipment while GST amount shall be reimbursed for sourcing of materials within the country on submission of documentary evidence. The exemption applies strictly to direct input materials and equipment. For further details, refer Renewable Energy Tax Exemption Act of Bhutan 2026 (www.mof.gov.bt). |
| 127 | Section IX- Particular Conditions, Part B - Special Provisions, sub clause 14.8 | Kindly define "Arrears"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Payment arrears refer to recovering or paying certified yet unpaid interim payments or outstanding balances or missed bills or differentials.                                                                                                                                                                                                                                                                       |
| 128 | Section IX- Particular Conditions, Part B - Special Provisions, sub clause 13.7 | 1. As per the notification dated 15th June 2026 published by Economic Advisor, Govt. of India, the base for various index is 2022-23 = 100, whereas the clause provides 2024=100.Kindly review the base year and confirm.2. Source of Index for various items such as Oxygen gas, electrodes, steel, machinery & machine tools as specified in the clause (i.e. Steel long, steel flat, basic inorganic chemical etc.) is not available in the index number of wholesale price published by Economic Advisor, Govt. of India Base 2022-23=100.Kindly review the same and confirm. | Provided as Annexure DCP-I(e)                                                                                                                                                                                                                                                                                                                                                                                       |
| 129 | Section IX- Particular Conditions, Part B - Special Provisions, sub clause 19.2 | We kindly request you to provide a copy of the Insurance Policy to be obtained by the Employer, in order to review the exclusions as well as the applicable terms and conditions of the policy.                                                                                                                                                                                                                                                                                                                                                                                   | Owner Controlled Insurance Program under process and refer Section IX-Particular Conditions, Part B Special Provisions Sub Clause 19.1 and 19.2 for insurance requirements.                                                                                                                                                                                                                                         |


**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                           | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|-----|------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 130 | Royalty rates                                        | We request you to kindly provide the royalty rates applicable to the project.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | For Royalty, refer Mines and Minerals Management Act 1995 and Mines and Minerals Management Regulations 2022                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| 131 | Electricity Charges                                  | We request you to kindly provide the electricity charges/tariff applicable for the project.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | For electricity tariff, visit website of Bhutan Power Corporation: <a href="http://www.bpc.bt">www.bpc.bt</a>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| 132 | Section II- Bid Data Sheet, ITB 7.4                  | We request you to kindly confirm the date and time of the pre-bid meeting. Further, we request that a provision be made for online participation through virtual mode to enable wider participation by prospective bidders.                                                                                                                                                                                                                                                                                                                                                                                                           | Virtual/Physical Pre-Bid Meeting conducted as per the provisions of the Bidding Document.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| 133 | Section I- Instruction to Bidders (ITB), Clause 11.6 | Kindly arrange to provide the format of Joint Venture Agreement                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Bidder to adopt industry standard Joint Venture Agreement template in fulfilment of requirements specified under Bidding Document.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 134 | Section-III Clause A of EQC                          | <p>i) Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.35 million m3 in any one year in a Dam/Weir/Barrage in the last 20 years in a single project</p> <p>ii) Successfully achieved open excavation for abutments &amp; foundation for the Dam of minimum excavation volume 1.0 million m3 in any one year in the last 20 years in a single project.</p> <p>iii) Experience of having excavated an underground tunnel and concrete lining works of at least 1.3 km length having finished diameter of 7 m or more in the last 20 years in a single project.</p> | <p>Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i), 4.2(ii) and 4.2(iii) are hereby amended as:</p> <p>4.2(i) "Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m3 in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.</p> <p>The Dam height and progress of concreting can be met through two separate projects</p> <p>4.2(ii) Successfully achieved excavation for Dam/Barrage/Weir Complex for River Diversion of minimum excavation volume of 0.80 million m3 in any one year in the last 20 years in the single project.</p> <p>4.2(iii) Experience of having excavated an underground tunnel and concrete lining works of at least 1.3 km face length having finished diameter of 7 m or more in the last 20 years in a single project. Underground tunnel shall cover underground hydro/highway/railway/metro/irrigation project tunnels."</p> |
| 135 | Section-III Clause 1.4,1.5,1.6 & 1.7 of EQC          | We respectfully request the Employer to delete the Technical Evaluation point-based scoring criteria.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                      | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                                                                                                                                                                                                                    |
|-----|-----------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                 | Since bidders are already required to submit detailed Technical and Financial Proposals demonstrating compliance with the bidding requirements, the point-based evaluation may kindly be omitted.                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                               |
| 136 | Section II ,Sect-VIII and Sect-IX 49.1 and Cl No 4.2 of PCC/GCC | The successful Bidder shall be required to submit a separate unconditional Performance Guarantee that includes Performance Security (4%) and ES Performance Security (1%) of Accepted Contract Amount valid up to 30 (Thirty) days after taking over of Works. The bank guarantee shall be in favour of the Employer, issued by the Financial Institution of Bhutan or any foreign bank acceptable and enforceable by the Financial Institution of Bhutan. The Bidding Document specifies the release provisions only for the E&S Performance Security. Kindly confirm the Release of Performance Security. | Sub-Clause 4.3.2 under Section IX-Particular Conditions Part B Special Provisions is amended as<br>"Return of the Performance Security and E&S Performance Security"<br><br>In sub-paragraph (a) "21 days after the issue of the Performance Certificate" is replaced with: "30 days after issue of Taking Over Certificate." |
| 137 | Sect-VIII and Sect-IX Cl No 14.9 of PCC/GCC                     | The Employer shall return Retention Money/Bank Guarantee in lieu of Retention Money shall be released within 21 days after completion of the respective scope of works, as stipulated in the Bidding Document.                                                                                                                                                                                                                                                                                                                                                                                              | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                             |
| 138 | Sect-VIII and Sect-IX Cl No-8.1 PCC/GCC                         | We request the Employer to consider the date of handing over of the Site as the Commencement Date for the Contract.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                             |
| 139 | Sect-VIII and Sect-IX Cl No 14.7 of PCC/GCC                     | We request to amend as followsSubmitted by the Contractor in respect of Interim Payment Certificate, 90 % of the admissible gross value of Interim Payment Certificate on provisional basis within 7 days after Engineer receives the statement and supporting documents and after taking into account all recoveries including retention amount on 100 % of the value of Interim Payment                                                                                                                                                                                                                   | Clause 14.7b(i) under Section IX-Particular Conditions Part A Contract Data is hereby amended as follows:<br>"75% of the IPC within 7 days after the Engineer receives the Statement and supporting documents and the remaining 25% within 56 days after the Engineer receives the Statement and supporting documents."       |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|-----|--------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                            | Certificate. All the statutory deductions will be carried out on the amount payable to the Contractor. Balance 10% payment on any date between 7th day to 42nd day after the date of receipt of the statement and after taking into account of balance adjustment, statutory deductions & recoveries, if any                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| 140 | Sect-VIII and Sect-IX Cl No 2.6 of PCC/GC  | <p>The Bidding Document stipulates that the Employer shall provide the listed construction equipment to the Contractor at mobilization. Kindly confirm whether it is mandatory for the Contractor to take over all the construction equipment provided by the Employer. If mandatory, kindly clarify the procedure for transfer of ownership, payment, recovery mechanism, applicable taxes and duties, and the schedule of recovery from the Contractor.</p> <p>Kindly specify the relevant BOQ item number under which the recovery of Amount</p> | <p>It is mandatory for the contractor to take over all the minimum listed Employer's Equipment and the cost mentioned in Section IX- Particular Conditions, Part B-Special Provisions, Sub-Clause 2.6 shall be the applicable cost for the contractor and any additional cost shall be borne by the Employer.</p> <p>The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a))</p>                                                              |
| 141 | Sect-VIII and Sect-IX Cl No 2.6 of PCC/GC  | The Bidding Document states that the Employer-provided Construction Camp Facilities (CCF-1 & CCF-2) shall be recovered through the "(-ve) line item" in the BOQ. However, the corresponding BOQ item number(s) are not identified. Kindly specify the relevant negative BOQ item number(s) under which the recovery shall be made.                                                                                                                                                                                                                  | The line "The cost of the facilities has been indicated as (-ve) line item in the BoQ which shall be adjusted against the line item rates" is hereby deleted from Section IX-Particular Conditions, Part B-Special Provisions, Sub-Clause 2.7 on Pre-Fabricated Structure Residential Facilities at CCF-1 & CCF-2 and Section VII-Works' Requirement, Sub-Clause 6.2.2.1 and 6.2.2.2. The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)) |
| 142 | Sect-VIII and Sect-IX Cl No 4.30 of PCC/GC | We respectfully request the Employer to remove the Working Capital requirement from the bidding document, as it imposes a substantial financial burden on the Contractor by blocking significant funds throughout the contract period. This                                                                                                                                                                                                                                                                                                         | Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as""The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in                                                                                                                                                                                                                                                                                                          |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                                                                                   |
|-----|----------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                              | requirement adversely affects the Contractor's cash flow and increases the overall financing cost of the project. Further, as this is an Item Rate Contract, the Contractor will receive regular Monthly Running Account (RA) Bill payments based on the actual work executed. These periodic payments are sufficient to meet the project's working capital requirements and ensure smooth execution of the works. Therefore, maintaining an additional mandatory working capital deposit is not warranted. | an amount equivalent to one month of the equated monthly Accepted Contract Amount."                                                                                                          |
| 143 | CI No 02 of ITB                              | Kindly confirm whether the World Bank financing has already been approved. If the approval is still under process, please provide the current status, the expected timeline for obtaining the approval.                                                                                                                                                                                                                                                                                                     | World Bank Group financing has been approved on January 22, 2026.                                                                                                                            |
| 144 | General                                      | Kindly give us the timeline to issue the performance certificate                                                                                                                                                                                                                                                                                                                                                                                                                                            | The timeline to issue the Performance Certificate shall be governed by the General Conditions of FIDIC(RED) Book Second Edition 2017 (Reprinted 2022 with amendments) under Clause No. 11.9. |
| 145 | Sect-VIII and Sect-IX CI No 8.8 of PCC/GC    | Kindly Amend and Limited to 5% of the Contract Price                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Provisions of the Bidding Document shall prevail.                                                                                                                                            |
| 146 | Sect-VIII and Sect-IX CL No. 12.3 of PCC/GCC | (b)(i) The measured quantity of an item is changed by more than 20% from the quantity of this item in the Bill of Quantities or other schedule.                                                                                                                                                                                                                                                                                                                                                             | Provisions of the Bidding Document shall prevail.                                                                                                                                            |
| 147 | General                                      | We kindly request the Employer to provide a separate payment structures for Hydro Mechanical Works. This will facilitate better planning, efficient execution, and smooth progress of the Works.                                                                                                                                                                                                                                                                                                            | Provisions of the Bidding Document shall prevail.                                                                                                                                            |
| 148 | Sect-VII CI No 6.8 of Works Requirements     | The Bidding Document states that the Employer will provide the 33/0.415 kV distribution transformers at locations near the work sites. We understand that the construction power supply is on a chargeable basis. Kindly provide the applicable electricity tariff/rates, connection charges, and any other applicable charges to                                                                                                                                                                           | For electricity tariff, visit website of Bhutan Power Corporation: <a href="http://www.bpc.bt">www.bpc.bt</a>                                                                                |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                               | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                            |
|-----|------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                          | enable the Contractor to estimate the cost accurately                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                       |
| 149 | General                                  | We request to update/status of the Environmental, Forest and Other clearances                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation & Resettlement has been completed for the lands identified for the work under the Package.                                                                                                                                         |
| 150 | General                                  | We kindly request to extend the Bid Due Date by one (1) month from the current deadline of 28.07.2026, as the ongoing monsoon season is causing delays in site visits and bid preparation activities. The requested extension will enable bidders to submit competitive bid.                                                                                                                                                                                                                                                                                                                                                                                                                                                          | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs.                                                                                                                                                                                                                                                                                                                             |
| 151 | Part 1, Section III, Page 57, Clause 4.2 | We understand that the said requirement may be demonstrated through separate projects, i.e.:1) Experience of construction of a dam of minimum height of 85 m may be demonstrated from one completed Dam project; and2) Annual concreting progress of 0.65 million cum in any one year may be demonstrated from another Dam I Weir I Barrage project executed within the last 20 years.Both capabilities are relevant to the proposed work, but they measure different aspects of execution experience and also one capability is allowed only through dam works and other allows Dam/Barrage/Weir experience, therefore we understand it can be met through separate projects.Request to clarify if bidders understanding is correct. | Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i) is hereby amended as:<br>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m3 in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.The Dam height and progress of concreting can be met through two separate projects" |
| 152 | Part 1, Section III, Page 57, Clause 4.2 | The requirement of achieving annual concreting progress of 0.65 million cum is primarily a function of resources, construction methodology, batching and placement capacity, and overall construction schedule and site conditions.However, very few conventional                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                       |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                               | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Addendum and Clarification                                                                                                                                                                                                                                                                        |
|-----|------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                          | concrete dam projects have yearly concrete quantities of this magnitude. Therefore, Experience of equivalent concrete quantity in single hydro project involving a dam may be a relevant measure. Therefore , we request to modify the clause as follows:1) Experience of having constructed the dam of minimum height of 85 m in one project and2) Achieved total concreting of 0.65 million cum in the same or another Hydropower project involving a concrete Dam in the last 20 years.This will allow wider and more competitive participation without diluting the intent of the qualification requirement.                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                   |
| 153 | Part 1, Section III, Page 57, Clause 4.2 | Open excavation productivity is primarily a function of equipment deployment, access planning, haulage arrangement, excavation methodology, muck disposal capacity, and overall project logistics.In a Hydropower project. large-scale open excavation is required across multiple critical fronts such as dam abutments, dam foundation, approach areas, intake, surface powerhouse, spillway and other associated structures. Therefore, the capability to achieve 1.3 million m' excavation in any one year in a single Hydropower project and not necessarily abutment and foundation, adequately demonstrates the bidder's resource mobilisation and execution capacity.Accordingly, we request that the criterion be modified to allow open excavation of minimum 1.3 million in any one year in a single Hydropower project, instead of restricting only to abutments and foundation for the dam. | Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(ii) is hereby amended as:<br>"Successfully achieved excavation for Dam/Barrage/Weir for River Diversion components of minimum excavation volume of 0.80 million m3 in any one year in the last 20 years in the single project." |
| 154 | Part 1, Section II, Page 40 ITB 4.1      | Please clarify the meaning of "relevant experience". Does it mean one Completed and Commissioned Hydropower Project involving a                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | ITB 4.1 under Section-II Bid Data Sheet is hereby amended as"Maximum number of members including the Lead Member in the Joint Venture (JV) shall be 2 (Two). At Least one JV                                                                                                                      |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                     | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                          | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----|------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                | Dam. Request you to confirm that the Bidders understanding is correct.                                                                                                                                                                                                                                                                                                                                                                                     | member shall have experience in construction of hydropower project in the Himalayan Region. For construction of head race tunnel, experience in construction of road tunnel, metros, railway tunnels in Himalayan Region shall also be acceptable."                                                                                                                                                                                                                                                                     |
| 155 | Part 1, Section II, Page 45 ITB 32.2                                                           | We understand that bidders are permitted to nominate the same Key Personnel for all three packages, considering that only one package will be awarded to a bidder, even if the bidder emerges as the lowest evaluated (L 1) bidder for more than one package.                                                                                                                                                                                              | Refer Section II-Bid Data Sheet Sub-Clause ITB 32.2, i.e., Key Manpower and Equipment resources may be shared across all the three packages, DCP-I, DCP-II and DCP-III, however, the unique requirements of each package shall be met independently                                                                                                                                                                                                                                                                     |
| 156 | Part 1, Section II, Page 46 ITB 45                                                             | Kindly clarify the award methodology for the remaining package(s). Specifically, if the original L1 bidder is not awarded a particular package due to this provision, will the package be awarded to the L2 bidder at its quoted bid price, or will the L2 bidder be required to match the L1 bid price as a condition for award?<br><br>And if L2 bidder refuses to match his bid price to L1 price then will the Employer ask L3 bidder for negotiation? | Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:<br>The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer. |
| 157 | Part 3, Section IX, Page 236 Clause No.6.2                                                     | Kindly clarify the mechanism for recovery of the cost of the Employer's Equipment from the Contractor. Further, please confirm whether the ownership of such equipment will be transferred to the Contractor upon full recovery of the amount & how? Also, we request you to provide us the makes of the Equipment that will be provided so as to consider the spare parts accordingly.                                                                    | The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)). Refer Section IX-Particular Conditions, Part B-Special Provisions, Sub-Clause 2.6. The Details of equipment has been provided as Annexure DCP-I(d).                                                                                                                                              |
| 158 | Part 3, Section IX, Page 231 Clause No.21.1<br><br>Part 1, Section I, Page 20, Clause No. 11.5 | We understand from the Particular Conditions and the Bid Data Sheet that the list of proposed DAAB members is to be submitted within 14 days from the date of notification by either Party requesting the appointment of the DAAB, which                                                                                                                                                                                                                   | The provision under Section II, Bid Data Sheet, ITB Clause 11.5 is amended as under:<br>"Appointment of DAAB member by either party: Within 42 days from the date of notification for a request for appointment of DAAB."                                                                                                                                                                                                                                                                                               |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                       | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Addendum and Clarification                                                                                                                                              |
|-----|--------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     | Part 1, Section II, Page 42, Clause No. ITB 11.5 | would be after the award of the Contract. However, Clause 11.15 of the Document Comprising the Bid requires the Bidder to furnish the names of three potential DAAB members along with their curriculum vitae as part of the bid submission.<br><br>Kindly clarify whether the list of proposed DAAB members and their curriculum vitae are required to be submitted at the bid stage, or whether the same shall be submitted after the award of the Contract in accordance with the Particular Conditions and the Bid Data Sheet. |                                                                                                                                                                         |
| 159 | Part 3, Section IX, Page 279 Clause No.14.9      | We request that the Retention Money Bank Guarantee be released upon issuance of the Performance Certificate, instead of remaining valid until 90 days beyond the Defects Notification Period.                                                                                                                                                                                                                                                                                                                                      | Refer Section IX- Particular Conditions Part B Special Provision Sub-Clause 14.9                                                                                        |
| 160 | Part 2, Section VII, Page 156 Clause No.14.9     | The tender document refers to Annexure 5.2 containing the overall project layout drawing and the KMZ file showing the access road, muck disposal area, quarry, and land earmarked for Contractor's Construction Facilities (CCFs). However, Annexure 5.2 is not included with the tender documents.<br><br>Kindly provide Annexure 5.2, including the project layout drawing and the corresponding KMZ file.                                                                                                                       | KMZ file shared as Annexure: DCP-I(a)                                                                                                                                   |
| 161 | Part 3, Section IX, Page 256 Clause No.7.8       | We understand that any change in royalty will be covered under the clause 13.7 Adjustment for Change in Law. Kindly confirm.                                                                                                                                                                                                                                                                                                                                                                                                       | Yes                                                                                                                                                                     |
| 162 | Part 3, Section IX, Page 230, Clause No.14.7b(i) | According to the aforementioned clause the IPC shall be issued within 14 days (56-42) after receiving statement and supporting documents                                                                                                                                                                                                                                                                                                                                                                                           | Clause 14.7b(i) under Section IX-Particular Conditions Part A Contract Data is hereby amended as follows: "75% of the IPC within 7 days after the Engineer receives the |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                         | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                             |
|-----|----------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                    | from contractor and the payment will be paid within 42 days after receiving the certification. Kindly confirm if our understanding is correct                                                                                                                                                                                                                                                                                                                                             | Statement and supporting documents and the remaining 25% within 56 days after the Engineer receives the Statement and supporting documents."                                                                                                                                                                                                                                           |
| 163 | Part 3, Section IX, Page 257, Clause No.4.30       | We respectfully request that this provision be deleted, as the requirement to deposit and maintain working capital equivalent to three (3) months of the equated monthly Accepted Contract Amount in the Escrow Account would substantially constrain the Contractor's working capital, adversely affect cash flow, and impose an undue financial burden during the execution of the Works.                                                                                               | Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as""The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in an amount equivalent to one month of the equated monthly Accepted Contract Amount." |
| 164 | Part 3, Section IX, Page 230, Clause No.8.8        | We understand that the delay damages i.e. 0.35% per week is for delay in completion of whole works.                                                                                                                                                                                                                                                                                                                                                                                       | Yes                                                                                                                                                                                                                                                                                                                                                                                    |
| 165 | Part 3, Section IX, Page 255 & 256, Clause No.4.29 | The amount of LD per week of the Delay as a % of the Contract Amount in milestones table is specified as: 0.35% subject to a maximum of 10% taken cumulatively for all milestones. However, if calculated as per the formula given in tender the LD per week of delay of each milestone (%) will be different (not 0.35%). Kindly clarify the LD per week (%) for each milestone.                                                                                                         | Revised Sub-Clause 4.29 under Section IX-Particular Conditions, Part B Special Provisions is attached as Annexure DCP-I(g).                                                                                                                                                                                                                                                            |
| 166 | Part 2, Section VII, Page 220--223                 | We understand that resumes of all Key Personnel for the Civil Works are also required to be submitted, as the Technical Evaluation criteria include assessment of the Key Personnel for the Civil Works. However, the relevant note specifically mentions submission of resumes only for the Key Personnel related to ES & OHS.Kindly clarify whether resumes are required to be submitted for all Key Personnel including for the Civil Works or only for the E&S and OHS Key Personnel. | Refer Section II-Bid Data Sheet Sub-Clause ITB 32.2, i.e., Key Manpower and Equipment resources may be shared across all the three packages, DCP-I, DCP-II and DCP-III, however, the unique requirements of each package shall be met independently. Resume required to be submitted for all Key Personnel including E&S and OHS Key Personnel.                                        |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Addendum and Clarification                                                                                                                                                                                                                      |
|-----|-------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 167 | Part 3, Section IX, Page 255, Clause No.4.29                                  | Kindly confirm whether the required quantity for completion of delivery at site is two (2) or four (4) spillway radial gates, including all associated components.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Replace the word "two (4) numbers" with "Six (6) numbers" under Section IX-Particular Conditions, Part B- Special Provisions Sub-Clause 4.29 (DCP-I-M6).                                                                                        |
| 168 | Annexure-7, Page No.8 Clause No. DHPP-CD-2026-103                             | 1. Diaphragm Cut-off wall is shown at the downstream side of downstream cofferdam at river bed level. Working at the River bed level will be difficult because of existing water level. We request to revise the location of diaphragm cut-off wall at some elevation in main cofferdam body with compacted earth fill till riverbed level. (Similar to U/S coffer dam cut-off wall body with compacted earth fill till riverbed level. (Similar to U/S coffer dam cut-off wall. 2. The top level of cut-off wall is shown to match the river bed level. Working of trench cutter requires a flat platform while working and while marching/shifting. The given profile will not allow equipment movement. We request to revise the top level of cutoff wall in same level within main cofferdam body above river water level. | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. |
| 169 | Part 2, Section VII, Page No.138 & 154, 4. Salient features and 7.2 Runoff    | Kindly provide lean period river water level at U/S and D/S coffer dam.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | River Discharge is provided as Annexure DCP-I(f)                                                                                                                                                                                                |
| 170 | Annexure-7, Page No.8, Clause No. DHPP-CD· DAM-2026· 101· 750-DAM·D· SP-001-C | We presume, the construction of main road tunnel is already under execution by other contractor and not in the scope of Contract package I (DCP-1) for Dam. Please confirm for our understanding.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | The final lining of the road tunnel falls within the scope of DCP-I, whereas the tunnel excavation works are being executed by another contractor under the Pre-Construction Work package currently in progress.                                |
| 171 | Part 3, Section IX, Page 255, Sub-Clause No.4.29 Milestone                    | We presume that all the milestones are to be calculated from commencement date only. i.e., ("The Commencement Date shall be 28 days after the Contractor receives the Letter of Acceptance.")                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Yes                                                                                                                                                                                                                                             |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                | Addendum and Clarification                                                                                                                                                                                                                                                                       |
|-----|--------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 172 | Part 3, Section IX, Page 255, Sub-Clause No.4.29 Milestone   | Kindly clarify the Description of the Milestone with respect to project/HM components in detail for better understanding (eg. Intake Gates, etc.).                                                                                                                                                                               | Provision of the Bidding Document shall prevail.                                                                                                                                                                                                                                                 |
| 173 | Part 3, Section IX, Page 255, Sub-Clause No.4.29 Milestone   | Kindly clarify the interpretation of the milestone in respect to Spillway Radial Gates numbers.                                                                                                                                                                                                                                  | Replace the word "two (4) numbers" with "Six (6) numbers" under Section IX-Particular Conditions, Part B- Special Provisions Sub-Clause 4.29 (DCP-I-M6)                                                                                                                                          |
| 174 | Part 1, Section III, Page 48, Clause No.1.5                  | As per the minimum equipment list in aforementioned table, it appears that the drill rig with make and model (Baur BG-28H) is typographical error, as per our understanding and based on the scope as defined in the tender document, we do not envisage deployment of drill rig/piling rig during construction. Please clarify. | Drill Rig is required for the construction of the coffer dams.                                                                                                                                                                                                                                   |
| 175 | Part 2, Section VII, Page 157, Clause No.9.1.1               | We request to provide us the Autocad File of Annexure 5.1 for our detailed analysis.                                                                                                                                                                                                                                             | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)                                                                                                                                                                                                                           |
| 176 | Part 2, Section VII, Page 135, Clause No.DHPP-INFRA-2024-002 | Land for temporary establishment seems to be very far from the dam location, we request client to identify and allocate/allot land near the dam location.<br>Considering the requirement of concrete for dam, we request to provide the land for setting up of batching plant and crushing plant near the dam location.          | The bidder to prepare the bid in line with the available information in the Bidding Document. An additional space for the batching plant has been provided at the Cofferdam location for catering the concrete supply for the RCC dam concreting as indicated in the Annexure DCP-I(a) KMZ file. |
| 177 | Part 3, Section IX, Page 267, Clause No.8.30                 | We request to provide client's consideration of construction schedule for our reference.                                                                                                                                                                                                                                         | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period.                                                  |
| 178 | Part 2, Section VII, Page 156, Clause No.8                   | The Annexure 5.2 as mentioned in aforementioned clause is not available with the tender document. We request you to kindly provide the kmz file.                                                                                                                                                                                 | KMZ file shared as Annexure: DCP-I(a)                                                                                                                                                                                                                                                            |
| 179 | Section: General                                             | We presume that the encumbrance free land shall be handed over to contractor during construction (including tree cutting, forest clearances)                                                                                                                                                                                     | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation &                                                                                                                             |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                              | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Addendum and Clarification                                                                                                                                                                                                      |
|-----|---------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                         | environment clearances, etc.). For permanent scope locations and contractor's temporary facility area which will be handed over by the employer to the contractor.<br>Please confirm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Resettlement has been completed for the lands identified for the work under the Package.                                                                                                                                        |
| 180 | Section: General                                                                                        | Construction of Closure dyke at U/S coffer dam comprising of (1 B) Well graded Sand (SW)/IGravel (GW), and (1A) Silty sand (SM)+ 15% silt/ fat clay (CH) will be difficult in flowing river.<br>Hence, we request to introduce separately payable pre-coffer dam/dyke of rockfill material to enable construction of main Upstream and Downstream Cofferdam.                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Provision of the Bidding Document shall prevail.                                                                                                                                                                                |
| 181 | Annexure-6, Section B.22, Page No.63, 64, Clause No.22.12 & DHPP-HM-DAM-2026-105; DHPP-HM-DAM-2026-107; | PTS design-data tables state the clear opening for both the auxiliary spillway stoplog and the auxiliary spillway service gate as 5 m (W) x 5.8 m (H). The corresponding GA drawings (Salient Features tables) show the clear opening as 5.0 m (W) x 15 m (H) for auxiliary spillway service gate - i.e. a difference of 9.2 m in height. Sill EL.844.50 m and design water level EL.850.00 m are common to both documents, so the discrepancy is confined to the stated clear height. Please confirm the correct clear opening height for the Auxiliary Spillway Service Gate - 15 m as per the GA drawings, or 5.8 m as per the PTS design-data table - and issue a revised/corrected data sheet or drawing so that gate leaf area, seal length, hoist capacity and BOQ quantities can be worked out on a consistent basis. | The auxiliary spillway service gate of clear opening of 5.0mx5.8m with sill level at EL.844.50 m. The clear opening is 5.8 m as per PTS. The DWG has been modified accordingly.                                                 |
| 182 | Annexure-6, Section B.22, Page No.53,55, Clause No.22.11 & DHPP-HM-DAM-2026-101/102                     | The design-data table immediately below the page 53 states 'Number of stoplog sets: 1', while the narrative under Cl. 22.11.3.2 (Page 55) states 'The total number of stoplogs (2 sets) will allow the                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | The number of stoplogs set has been confirmed as 1. The text (Particular Technical Specification (PTS) and BoQ) have been modified accordingly. Amended BoQ and PTS is attached as Annexure DCP-I(h) and DCP-I(i) respectively. |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Addendum and Clarification                                                                                                                                                 |
|-----|--------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                              | <p>maintenance of two radial gates at the same time.' The GA drawing's Salient Features table lists 'NO OF GATE: 1' (7-element stack) without indicating how many such complete sets are to be supplied. Please clarify and confirm, in a single consistent statement, the exact number of complete Spillway Stoplog sets (each of 7 elements) to be furnished under this contract - one (1) set or two (2) sets - as this materially affects the BOO quantity, embedded-parts count (currently shown as six (6) sets, one per opening) and pricing.</p>                                                                                                                                                                                                                                          |                                                                                                                                                                            |
| 183 | Annexure-6, Section B.22, Page No.65&95, Clause No.22.12.3.3 | <p>The PTS describes an Environmental Flow Release System (3 No. embedded pipes, 450 mm dia., inlet EL.838.0 m, outlet EL.825.0 m, located in the Auxiliary Spillway Bay, complete with inlet trash rack) forming part of the H&amp;M scope of supply, to be paid on a lump-sum basis after commissioning. No GA or detail drawing for this system (pipe layout, embedded parts, inlet trash rack, isolated control arrangement) is included in the issued 14 -sheet HM drawing package. Please issue the GA and detail drawings (or, at minimum, a preliminary layout/schematic) for the Environmental Flow Release System, including pipe routing, embedded parts, inlet trash rack and any control/isolation valves, so that this lump-sum item can be realistically estimated and priced.</p> | <p>The detailed drawings will be available only in the detailed design stage. The pipe routing as indicated in the dam sectional drawings may be referred for pricing.</p> |
| 184 | Annexure-6, Section B.22, Page No.2, Clause No.22.1.2        | <p>The general scope of work lists 'One (1) door for Adit 1' as an item to be supplied under this contract. No design data (size, type, sill/invert level, design head, hoisting arrangement) or GA drawing for this door is provided in either the PTS Particular Specifications (Cl. 22.11-22.15, which cover only Spillway, Auxiliary Spillway, Intake Gates, Trash Rack/ TRCM and Cranes) or the</p>                                                                                                                                                                                                                                                                                                                                                                                          | <p>Please refer to DWG DHPP-CD-ADT-2026-109. The document has been modified accordingly.</p>                                                                               |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                         | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-----|--------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                    | drawing package. Please furnish the size, invert/sill level, design head, gate/door type and operating arrangement for the Adit-1 door, together with a GA drawing, or confirm that it is covered under a separate specification/drawing package to be issued subsequently.                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 185 | Annexure-6, Section B.22, Page No.56 & 95, Clause No.22.11.4       | The steel liner on the spillway glacis, piers and breast wall is stated to be measured and paid for on a weight (kg) basis, but neither the PTS nor the issued GA/section drawings indicate the extent (developed area) or any other basis from which an indicative tonnage can be derived for bidding purposes. Material of liner (if preferred) has not been mentioned also. Please provide an indicative developed surface area and preferred material (if any) (or an indicative tonnage) for the spillway glacis/pier/breast-wall steel liner, to enable bidders to price this weight-based BOQ item on a common and consistent basis.                                                                         | Indicative tonnage is specified in the BoQ. Please refer to drawing DHPP - CD - DAM - 2026 -104                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 186 | Annexure-6, Section B.22, Page No.66, 55 & 74, Clause No.22.12.4.2 | For the Spillway and Intake gates, the PTS specifies seals of synthetic rubber 'made of SBR (Styrene Butadiene Rubber)' only. For the Auxiliary Spillway gate/stoplog, the same clause is written as 'synthetic rubber made of EPDM /SBR (Styrene Butadiene Rubber)'. EPDM and SBR are different elastomers with different technical properties (ozone/UV resistance, temperature range); describing EPDM as 'SBR' is technically inconsistent. Please confirm the intended seal material for the Auxiliary Spillway gate and stoplog - EPDM or SBR - and, if EPDM is acceptable/preferred, provide the applicable EPDM property requirements (hardness, tensile strength, elongation, ozone resistance) separately | The Particular Technical Specifications shall take precedence over the General Technical Specifications. Where the Particular Technical Specifications do not specify a particular elastomer, the requirements of the General Technical Specifications shall apply. Accordingly, under the General Technical Specifications, no specific elastomer type is mandated, and bidders may propose seals manufactured from either SBR or EPDM, provided that the selected material is suitable for the intended service conditions and complies with the applicable performance and quality requirements" |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                 | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                               |
|-----|--------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                            | from the SBR properties currently tabulated, so bidders can quote compliant seals.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                          |
| 187 | Annexure-7, Clause No.DHPP-HM-DAM-2026-103 | In section - 1, Radius is mentioned as 18000 mm measured from Trunnion centre to D/S flange of curved vertical stiffeners. Whereas, it is mentioned as 18000 mm from trunnion centre to inside of skin plate.Please correct any one of the two statements. In our experience Radius should be proposed from outside of skin plate which ensures a perfectly fixed, smooth sealing surface that maintains constant contact and uniform compression with the top seal at any gate position.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Please refer to the BoQ, drawings, and technical specifications included in the Tender Package.The radius for the top-seal shall be measured from the outside surface of the skin plate to ensure constant, uniform seal contact at every gate position. |
| 188 | Annexure-7, Clause No.DHPP-HM-DAM-2026-104 | Detail - B, it has been shown that one double stem type rubber seal is fixed with the lintel (lintel seal) and other is fixed with the gate (gate seal). The gate seal is being compressed by water pressure pipes.In our opinion, the proposed arrangement will introduce severe operational challenges over time. In the long run, the water-pressure pipes are highly susceptible to silt accumulation and choking, which will ultimately hamper the pre-compression of the gate seal. Furthermore, Forward movement of the skin plate due to thermal expansion of arms creates a high risk of fouling with the lintel seal clamps. Conversely, Backward movement of the skin plate during thermal contraction reduces pre-compression in rubber seals, causing the lintel and gate seals to lose contact with skin plate and lintel seal invert, resulting in leakage.To mitigate these risks, we recommend adopting a field-proven arrangement implemented over a decade ago at NHPC's Teesta-V and TLDP-III Hydroelectric Projects in INDIA. This arrangement utilizes a spring-loaded (conveyor belt) lintel seal, which successfully | Please refer to the BoQ, drawings, and technical specifications included in the Tender Package.                                                                                                                                                          |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                          | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Addendum and Clarification                                                                                                                                                                                                  |
|-----|---------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                     | accommodates thermal movement and eliminates siltation risks. We request that this alternative be considered for this project & the drawing be revised accordingly.                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                             |
| 189 | Annexure-7, Clause No.DHPP-HM-DAM-2026-104                          | In Plan 807.2, it has been shown that Cardenic support structure is placed over the Arm as if hydraulic cylinder is connected somewhere near to top arm but in fact the cylinder is connected with bottom intermediate arm, so this view is not correct. There should be enough space between the arm & pier for free movement of cylinder.As per Plan 807.2, the distance between the centre line of end arm & pier is only $(9000 - 7500)/2 = 750\text{mm}$ , merely we can have a clear space of 350 - 450 mm & this space is never sufficient to place a hydraulic cylinder. Please consider this matter & revise the drawing. | Please refer to the BoQ, drawings, and technical specifications included in the Tender Package.                                                                                                                             |
| 190 | Annexure-6, Section B.22, Page No. 54, Clause No. 22.11.3           | This Technical specification has mentioned nothing about this.<br><br>It is a normal practice that the Trunnion bush of the radial gate should be Self-lubricating type and its designing criteria (allowable stresses. Casting type, Alloy No., type of dry lubricants, etc.) must be mentioned. Please incorporate the same.                                                                                                                                                                                                                                                                                                     | The details of design criteria will be provided in the detailed design phase. Please refer to the drawings and technical specifications included in the Tender Package.                                                     |
| 191 | Annexure-6, Section B.22, Page No. 54, Clause No. 22.11.3           | This Technical specification has not mentioned this.It is always seen that the skin plate of such a Top seal radial gate is of stainless steel clad plate or pure stainless steel plate. Plain structural steel rusts and pits, destroys rubber seals and causes severe water leakage. So please clear the issue, it is a matter of huge price difference.                                                                                                                                                                                                                                                                         | Please refer to the technical specifications where it is stated "The side, the top and the bottom sealing plates will be stainless steel. Each gate will be operated by two oil operated servomotors. " (section 22.11.3.1) |
| 192 | Annexure-6, Section B.22, Page No. 5, 6, Clause No. 22.2.3 Sl. No.c | Some major vendors' names are missed out. They are always included In most of the Indian hydro power project tenders.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | The list of vendors provided in the specification is indicative only.                                                                                                                                                       |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                               | Clarifications Sought/Suggestions                                                                                                                                                                                                          | Addendum and Clarification                                                                                                                                                                                                                              |
|-----|------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                          | • Deva Glide Lubrite, INA & GGB" - may be added.                                                                                                                                                                                           |                                                                                                                                                                                                                                                         |
| 193 | Annexure-6, Section B.22, Page No. 88,89, Clause No. 22.15.2                             | This Technical specification has not mentioned the parameters like Hoisting speed, LT speed etc.<br><br>Please mention the same.                                                                                                           | These details are included in the gate design data. Additional information will be addressed in subsequent design phases.                                                                                                                               |
| 194 | Annexure-6, Section B.22, Page No. 72, 73, Clause No. 22.13.2 & 22.13.3.1                | As per PTS Cl. No.22.13.2 (pg. 72), operation speed= 0.3 m/min but as per PTS Cl. No.22.13.3.1 (pg. 73, last line), raising or lowering speed = 1.0 m/min + 5%.<br><br>Please confirm which one is correct.                                | Please consider 0.3 m/min. The document has been modified accordingly.                                                                                                                                                                                  |
| 195 | Annexure-6, Section B.22, Page No. 81, Clause No. 22.14.2 & Drg. No.DHPP-HM-DAM-2026-109 | There is no mention regarding Radius of TRCM Boom, neither in PTS Cl. No.22.14.2 (pg. 81) nor in related drawing No.: DHPP-HM-DAM-2026-109.<br><br>Please incorporate this.                                                                | This type of information will be addressed during the next phase of the design.                                                                                                                                                                         |
| 196 | Annexure-6, Section B.22, Page No. 80, Clause No. 22.14.2 & Drg. No.DHPP-HM-DAM-2026-109 | As per PTS Cl. No. 22.14.2 (pg. 80), Trash Rack angle respect to vertical is 10 degree but as per Key Section of Drg. No. : DHPP-HM-DAM-2026-109, this angle is 20 degree.Please correct any one of the two angles and revise accordingly. | The angle is 10 degree in both. In the Drawing No. DHPP-HM-DAM-2026-109 key section, 80 degree is shown and it is consistent with the Particular technical specifications.                                                                              |
| 197 | Section: General                                                                         | The PTS is missing criteria for permissible stresses for structural designing. Criteria for permissible stresses used in the structural design of Radial gates, vertical gates, l gates, embedded parts may please be included.            | The details of design criteria will be provided in the detailed design phase. Please refer to the drawings and technical specifications included in the Tender Package.                                                                                 |
| 198 | Section: General                                                                         | Feeder Points for H M Equipment are not mentioned in the PTS. Please provide No. of Feeder point and its location for estimation of Electrical items.                                                                                      | Feeder point shall be distributed from the Transformer point provided.<br>The additional scope of tapping of line from 33 kV trunk line, if required along with transformer and LV supply will be in contractor's scope upon approval from the Employer |
| 199 | Section: General                                                                         | There is no PLAN VIEW shown in any H & M Drawings.                                                                                                                                                                                         | Please refer to the drawings and technical specifications included in the Tender Package.                                                                                                                                                               |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                       | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                    | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                  | Without the Plan View, exact distances between the HM Equipment cannot be verified. This prevents the precise calculation of cable lengths and associated bulk materials. Please revise the H M Drawings accordingly.                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 200 | Section: General                                                 | There is no mention in PTS for Supply and Control Voltage. Supply and Control Voltage is required to built-up the circuit drawings of Electrical System. Please incorporate the same.                                                                                                                                                                                                                                                | Please refer to the drawings and technical specifications included in the Tender Package.                                                                                                                                                                                                                                                                                                                                         |
| 201 | Section: General                                                 | There is no detail regarding the Motor like, starting system, Duty class, insulating resistance etc.For detail engineering it is required, please provide.                                                                                                                                                                                                                                                                           | The details will be provided in the detailed design phase. Please refer to the technical specifications included in the Tender Package.                                                                                                                                                                                                                                                                                           |
| 202 | Request for Bid Doc, Page 12, Clause 2.1 Source of Fund          | 1. The statement mentions 'debt portion is proposed to be raised'. Kindly confirm whether Debt portion has already been arranged.<br>2. If answer to the above is yes, who is the lead financing agency?<br>3. Kindly clarify the modality of payment to EPC i.e. whether entire payment will be paid by the SPV?<br>4. In case SPV does not infuse its 30% equity at regular intervals, then, what will be the mechanism of payment | The Project will achieve financial closure before award of the Main Packages and International Finance Corporation has been identified as the Lead Arranger. The Payment to the Contractor will be made by the Employer directly and equity has been secured.                                                                                                                                                                     |
| 203 | Request for Bid Doc, Page 40, Section II-Bid Data Sheet; ITB 4.1 | As there is a conflict in clauses and as both are part of BDS, we request you to consider the clause 56 to be the criteria and change on page 40 as below:<br>"Joint Venture (existing or intended) - All Members Combined must meet requirement of relevant experience in construction of Hydropower"                                                                                                                               | ITB 4.1 under Section-II Bid Data Sheet is hereby amended as "Maximum number of members including the Lead Member in the Joint Venture (JV) shall be 2 (Two). At Least one JV member shall have experience in construction of hydropower project in the Himalayan Region. For construction of head race tunnel, experience in construction of road tunnel, metros, railway tunnels in Himalayan Region shall also be acceptable." |
| 204 | General Question                                                 | If a bidder has the required eligibility criteria for all the 3 packages; has sufficient bid capacity; and is                                                                                                                                                                                                                                                                                                                        | Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:"The Employer will award the Contract to the successful                                                                                                                                                                                                                                                                                                           |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                 |
|-----|---------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                               | the most responsive bidder in more than 1 package (e.g., if a bidder is lowest i.e., L 1 in all three packages) then, whether all three packages can be awarded to the same bidder?                                                                                                                                                                                                                                                                                                                                                          | bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer."                                              |
| 205 | Request for Bid Doc, Page 43 & 44, ITB 22.1                   | Considering the multifaceted nature and sophistication of these 3 packages, a comprehensive study is needed to prepare the most comprehensive bid(s). Therefore, we humbly request you to extend the deadline for Bid submission (for all the 3 packages) until September 30, 2026; Time: 15.00 hrs.                                                                                                                                                                                                                                         | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs                                                                                                                                                                                                                                                                                                                                                                   |
| 206 | Section-III – Evaluation and Qualification Criteria/ 4.1 (ii) | It is requested to modify the clause as below:<br>"ii) Hydro-Mechanical General Construction Work Experience in last 20 years with work value of a single completed work or up to five works more than BTN. 1,150 million" This modification will allow the bidder to qualify themselves, enabling them to quote competitively under a single point of responsibility and smoother interfaces. Consequently, this reduces reliance on the limited number of HM Sub-contractors who control the prices and commercial terms. Kindly consider. | Section III-Evaluation and Qualification Criteria; Sub-Clause: 4.1(ii); Page 56 of 319 is amended as under:<br>"Hydro-Mechanical General Construction Work Experience in last 20 years with work value of a single completed work/Substantially Completed work or up to five works more than BTN. 1,000 million. The substantially completed work shall be evaluated against submission of documentary evidence from the Client/Employer". |
| 207 | Section-III – Evaluation and Qualification Criteria/ 4.2 (i)  | It is requested to modify the criteria as below:<br>"i) Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.40 million m <sup>3</sup> in any one year in a Dam/Weir/Barrage in the last 20 years in a single the same project."                                                                                                                                                                                                                                            | Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i) is hereby amended as:<br>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m <sup>3</sup> in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.                                                                                                             |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Addendum and Clarification                                                                                                                                                                                                                                                                                                                         |
|-----|---------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                               | Kindly consider.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | The Dam height and progress of concreting can be met through two separate projects"                                                                                                                                                                                                                                                                |
| 208 | Section-III – Evaluation and Qualification Criteria/ 4.2 (ii) | It is requested to modify the criteria as below:<br>“ii) Successfully achieved open excavation for abutments & foundation for Hydro Project involving a Dam/ Barrage with minimum excavation volume of 1.3 million m3 in any one year in a single project completed in the last 20 years.”Kindly consider.                                                                                                                                                                                                                                                                                                                                   | Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(ii) is hereby amended as:<br>"Successfully achieved excavation for Dam/Barrage/Weir complex for River Diversion of minimum excavation volume of 0.80 million m3 in any one year in the last 20 years in the single project."                                                     |
| 209 | Section-III – Evaluation and Qualification Criteria/ 4.2 (iv) | It is requested to modify the criteria as below:<br>“(iv) Successfully carried out radial gate manufacture and erection of size of 54 m2 or more with a minimum head of 34 m complete with hydraulics hoisting system by its own or through Specialized Subcontractor in last 20 years in a single project.”<br><br>This modification will allow the bidder to qualify themselves, enabling them to quote competitively under a single point of responsibility and smoother interfaces. Consequently, this reduces reliance on the limited number of HM Sub-contractors who control the prices and commercial terms.<br><br>Kindly consider. | Section-III Evaluation and Qualification Criteria, Sub Clause 4.2(iv), is hereby amended as:<br>"Successfully carried out radial gate manufacture and erection of size of 50m2 or more with a minimum head of 30m complete with hydraulics hoisting system by its own or through Specialized Sub-contractor in last 20 years in a single project." |
| 210 | Section-III – Evaluation and Qualification Criteria/ 4.2 (iv) | It is requested to add the below mentioned clause in line with NHPC and other PSU tenders in India :For the portion of work executed through a sub-contractor, full experience for that portion of work can be claimed by the Contractor as well as sub-contractor for fulfilling criteria for evaluation of bidder’s experience”.This addition will allow the bidder to qualify themselves, enabling them to                                                                                                                                                                                                                                | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                           | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|-----|----------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                      | quote competitively under a single point of responsibility and smoother interfaces. Consequently, this reduces reliance on the limited number of HM Sub-contractors who control the prices and commercial terms. Kindly consider.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 211 | Sec-II, Bid Data Sheet, ITB, Cl. 19.1                                | <p>The amount of Bid Security is very high and kindly reduce the same. Also, we understand from the bid documents that, only one contract will be awarded to one bidder. Hence, we request to modify the clause for Bid Security as below:</p> <ul style="list-style-type: none"> <li>• Bid security shall be submitted for a single package for an amount of BTN/INR 100 million (Hundred Million) only.</li> <li>• The Bid Security shall be in the form of Bank Guarantee or Insurance Surety Bond.</li> <li>• If the Bidder is participating in more than one package, then, Bid Security shall be required for only one package and Bid Security Declaration shall be allowed for other Packages.</li> </ul> | <p>Section II-Bid Data Sheet Sub Clause 19.1 is hereby amended as:</p> <p>"A Bid Security shall be required. Bid must be accompanied by a Bid Security in the form an unconditional bank guarantee from any financial institution in Bhutan and India. The amount and currency of the Bid Security shall be BTN/INR 248 million (Two Hundred Forty-Eight million) only."</p>                                                                                                                                                         |
| 212 | Sec-II, Bid Data Sheet, ITB, Cl. 45                                  | We understand that, if one bidder is lowest in more than one package, one package will be awarded to the L1 bidder and the other package will be awarded to the L2 bidder. Please confirm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | <p>Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:</p> <p>"The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid. In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer."</p> |
| 213 | Sec-VII, Works's Requirements, IFB, Cl. 8                            | Annexure 5.2 is missing in the bid documents and kindly provide the same.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | KMZ file shared as Annexure: DCP-I(a)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| 214 | Drg. No. DHPP-CD-CD-2026-102<br>Sec-VII, Works' Requirement, IFB 9.5 | The drawing indicates requirement of impervious material for Cofferdam, whereas the table provided in IFB 9.5 does not include the details of                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Suitable impervious material is available at a source located approximately 50 km from the Dam Site.                                                                                                                                                                                                                                                                                                                                                                                                                                 |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                       | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                          | Addendum and Clarification                                                                                                                                                                                                                                                                                                             |
|-----|----------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                  | source. Kindly clarify the location & distance of borrow area for sourcing the impervious material.                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                        |
| 215 | Sec-VIII, GCC, Cl. 4.2.1                                                         | We request to consider validity/release of performance bank guarantee on completion of works, as the retention Money is also kept till 90 days beyond completion of Defect Notification Period, as per PCC 14.9.                                                                                                                                                                           | Sub-Clause 4.3.2 under Section IX-Particular Conditions Part B Special Provisions is amended as "Return of the Performance Security and E&S Performance Security"<br><br>In sub-paragraph (a) "21 days after the issue of the Performance Certificate" is replaced with: "30 days after the issue of Taking Over Certificate."         |
| 216 | Sec-VIII, GCC, Cl. 4.13                                                          | The responsibility of providing encumbrance free rights-of-way for the execution of the project free of cost to the Contractor shall remain with the Employer. Please modify the clause accordingly.                                                                                                                                                                                       | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation & Resettlement has been completed for the lands identified for the work under the Package. For the remaining, the provisions of the Bidding Document shall prevail. |
| 217 | Sec-XIII, GCC, Cl. 18.1                                                          | Sub-clause (f) may be modified as "natural catastrophes such as earthquake, tsunami, volcanic activity, hurricane, typhoon, landslides, floods, cloud bursts etc."                                                                                                                                                                                                                         | Clause 18.1 Sub-Clause(f) of GCC is amended including the exceptional events such as landslides, floods and cloud burst.                                                                                                                                                                                                               |
| 218 | Sec-IX, Part A, Contract Data, Cl. 8.8<br>Sec-IX, Part A, Contract Data, Cl. 8.8 | We understand that the % mentioned shall apply for the delay against the milestones as well as overall completion. In this matter, we suggest that the delay damages against the milestones shall be reduced as per the industry standards to 0.035% per week limited to 5% of the Contract Price.                                                                                         | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                      |
| 219 | Sec-IX, Part A, Contract Data, Cl. 14.6.2                                        | The progress of work achieved during the initial stage of the project and during monsoon may be considerably low in the project. In view of this, the minimum 0.5% defined for the interim payment shall be removed or reduced to 0.1% to ensure that the Contractor gets monthly payment for maintaining smooth cash flow in the project which otherwise may hamper the project progress. | Clause 14.6.2 of Section-IX Particular Conditions Part A, Contract Data (Page 230 of 319) is hereby amended as "0.25% of the Accepted Contract Amount for the initial period of 1 (one) year from Commencement Date and thereafter 0.50 % of the Accepted Contract Amount shall apply "                                                |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                  |
|-----|----------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------|
| 220 | Sec-IX, Part B, Special Provisions, Cl. 4.2  | Kindly reduce the Performance Security to 5% in view of the current industry practice.<br><br>Kindly allow Insurance Surety Bonds against Performance Security as an additional option for the Bidder.                                                                                                      | Provisions of the Bidding Document shall prevail.                                                                           |
| 221 | Sec-IX, Part B, Special Provisions, Cl. 4.19 | Kindly confirm the applicable energy charges/tariff with demand charges to be paid against consumption of power.                                                                                                                                                                                            | For electricity tariff, visit website of Bhutan Power Corporation: <a href="http://www.bpc.bt">www.bpc.bt</a>               |
| 222 | Sec-IX, Part B, Special Provisions, Cl. 7.8  | 1. Kindly clarify the prevailing rates of royalties for various materials like earth, Rock, Aggregates etc.<br>2. We understand that the royalty is not payable on material from demolition and excavations which are dumped within the dumping yard provided by the Employer. Pls clarify.                 | For Royalty, refer Mines and Minerals Management Act 1995 and Mines and Minerals Management Regulations 2022                |
| 223 | Sec-IX, Part B, Special Provisions, Cl. 8.5  | Kindly delete/modify this clause so that the contractor shall be eligible for extension of time if contractor has already notified according to the contract conditions but could not submit the claim as per Clause 20.1 due to any unavoidable situations/ exigencies at site.                            | Provisions of the Bidding Document shall prevail.                                                                           |
| 224 | Sec-IX, Part B, Special Provisions, Cl. 12.3 | We request to define the process in case of reduction in quantities >30% than provided in the BOQ.                                                                                                                                                                                                          | No revision of rates shall be permitted in the event of negative deviation or reduction in quantities.                      |
| 225 | Sec-IX, Part A, Contract Data, Cl. 1.1.84    | In view of the volume of work involved in this package, the time for completion provided (49.39months) is very low. Also, it is noted that the time for completion provided for Package-3 is 1792days (58.93months). Hence, kindly increase the time for completion for this package to at least 54 months. | Provisions of the Bidding Document shall prevail.                                                                           |
| 226 | Sec-IX, Part B, Special Provisions, Cl. 4.29 | Kindly revise all milestones in view of the overall time for completion.                                                                                                                                                                                                                                    | Revised Sub-Clause 4.29 under Section IX-Particular Conditions, Part B Special Provisions is attached as Annexure DCP-I(g). |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                  | Addendum and Clarification                                                                                                                                                                                                                                                                  |
|-----|----------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 227 | Sec-IX, Part B, Special Provisions, Cl. 4.29 | As per the drawings indicated, the RCC is to be continued up to the top of the Dam, hence it will not be possible to achieve this milestone as written in the text in a period of 129 weeks. Kindly modify the text of this milestone as below: "Completion of placement of RCC up to EL 790.00m"                                                                                                                  | The RCC placement up to the top of the dam is applicable only to the non-overflow blocks. Accordingly, this milestone shall be deemed achieved upon completion of RCC placement up to Elevation (EL) 790 m, which is below the spillway level.                                              |
| 228 | Annexure-4<br>Bill-of-Quantities (BOQ)       | It appears that the quantity mentioned in the BOQ in "m3" is very high against this item.                                                                                                                                                                                                                                                                                                                          | Unit of Measurement for the Line Item A9.18 Slush Grout under Annexure 4 Bill of Quantities (Page 10 of 26) is hereby changed to "kg"                                                                                                                                                       |
| 229 | General                                      | Kindly provide the estimated price along with the year of price level.                                                                                                                                                                                                                                                                                                                                             | The Bidder is required to undertake necessary due diligence based on the available information.                                                                                                                                                                                             |
| 230 | General                                      | Kindly confirm the status of various clearances of the project like:<br>a) Environmental Clearance<br>b) Forest Clearance<br>c) Approval PIB / CCEA<br>d) Land Acquisition                                                                                                                                                                                                                                         | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation & Resettlement has been completed for the lands identified for the work under the Package.                               |
| 231 | General                                      | Kindly inform likely date of award of contract to plan for the resources according to the start date.                                                                                                                                                                                                                                                                                                              | October 2026                                                                                                                                                                                                                                                                                |
| 232 | Bid Data                                     | Since the project is very large and includes components with high complexity, the preparation of the bid including interaction with various specialized agencies/ equipment manufacturers and to derive a most competitive techno-commercial proposal will require considerable time and we request to extend the due date for bid submission at least by 2 months' time from the issue of pre-bid clarifications. | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs                                                                                                                                                                                                                    |
| 233 | Annexure-7, Clause No. Drawings              | Working platform is at level 782m and width indicated is 10.5m. As per execution requirement width of 22m - 25m shall be provided for safe execution of work for cutter arrangement.                                                                                                                                                                                                                               | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. The available width at level 782 m is 18 m. |
| 234 | Annexure-7, Clause No. Drawings              | We understand that the maximum depth of the Cut-Off Wall at the upstream cofferdam is 58m                                                                                                                                                                                                                                                                                                                          | Please refer to the BoQ included in the tender package. The quantity includes both U/S and D/S cofferdams.                                                                                                                                                                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                      | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                | Addendum and Clarification                                                                                                                                                                                                                      |
|-----|---------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                 | and the average depth is 43m, we request you to kindly review and confirm the indicated BOQ quantity.                                                                                                                                                                                            |                                                                                                                                                                                                                                                 |
| 235 | General                         | Request to kindly provide the detailed geological reports /borelogs Data for Upstream Cofferdam location.                                                                                                                                                                                        | Available GBR and GDR shared as Annexure: DCP-I(b)                                                                                                                                                                                              |
| 236 | General                         | Request you to kindly specify the tentative commencement date and schedule of Upstream cofferdam so as to plan the resources accordingly.                                                                                                                                                        | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. |
| 237 | General                         | Request to kindly share the monsoon data / Working Season so as to plan the construction methodology and execution schedule accordingly.                                                                                                                                                         | River Discharge is provided as Annexure DCP-I(f)                                                                                                                                                                                                |
| 238 | General                         | Request to kindly provide a site visit / route survey report to assess the feasibility for mobilization of heavy equipment to Project site such as trench cutter for cut-off wall.                                                                                                               | Refer Information for Bidders under Section VII- Works' Requirement.                                                                                                                                                                            |
| 239 | General                         | Request you to kindly provide the AutoCAD Drawings of Dam Area Contours and all other Drawings. This is required to carry out proper planning of Dam Excavation, Concreting and planning of temporary Roads.                                                                                     | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)                                                                                                                                                                          |
| 240 | Annexure-7, Clause No. Drawings | Request you to kindly issue Drawing showing Berms at different elevations as shown in Instrumentation Drawing Titled INSTRUMENTATION DETAILS SECTION ALING DAM AXIS, Drawing No. DHPP-CD-DAM-2026-122 / 750-DAM-D-SP-022-B                                                                       | A separate drawing will not be issued at this stage. However, the stripping limits, elevations, and bench details indicated in Instrumentation Drawing No. DHPP-CD-DAM-2026-122/750-DAM-D-SP-022-B may be referred to.                          |
| 241 | Annexure-7, Clause No. Drawings | We suggest that Drawings may be modified to suit Construction. We suggest that a 1 in 10 Slope for Adit while approaching HRT may be allowed so that Vehicles can ply in Adit with 1:10 slope. Further, the HRT excavation needs to be carried out in Heading and Benching (Full face not likely | The Contractor is free to adopt a suitable construction methodology. Accordingly, the connection between the Adit and the HRT shall be designed and executed in accordance with the Contractor's proposed work methodology.                     |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Addendum and Clarification                                                                                                                                                                                                            |
|-----|-----------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                               | to be suitable in large size tunnel in Himalayan Geology). This will require Adit Invert slope to maintained such that dumpers and other Equipment can move from Adit to HRT and also come out of HRT Heading. The HRT will be made full face after excavation has progressed in Heading for significant length of tunnel. Then the Adit may be excavated in Benching to match Adit Invert with HRT Invert.                                                                                          |                                                                                                                                                                                                                                       |
| 242 | Annexure 5.1                                                                                  | We understand that the Lands CCF2 and CCF1 are for establishing Contractor's facilities. Request you to kindly confirm whether a land for Contractor's Camp will be made available separately. The location of this land may also please be indicated.<br>Further, we understand that the land at Upstream of Dam will also be made available to the DCP-I Contractor. However, access to the DCP-I land after Dam excavation has commenced is not understood. Request you to kindly clarify please. | Contractor's Camps and Facilities (CCFs) are designated for the construction of contractor camps and associated facilities. Access to DCP-I Land will be provided via the Highway Road Tunnel, which is currently under construction. |
| 243 | Annexure-6, Technical Specifications Section B, 20, Clause 20.5.2, PDF Page No. 542 of 745    | We will explore manufacturers of such cement. However, we also request you to kindly suggest names of manufacturers already explored by the Employer, so that we can approach them for Quotations.                                                                                                                                                                                                                                                                                                   | Ultratech and Dalmia cement suppliers may be contacted for sourcing.                                                                                                                                                                  |
| 244 | General                                                                                       | Request you to kindly confirm whether the Diversion Tunnel is designed to divert monsoon flood discharge or it is only for non-monsoon discharge. This is essential for our Work Scheduling and Planning.                                                                                                                                                                                                                                                                                            | Yes, it is designed to 1 in 25-year monsoon flood.                                                                                                                                                                                    |
| 245 | RFB No.: Dorjilung / CPD/DCP-I/2026/874 issued on 13th June, 2026<br>Cl. 8, PDF Page 3 of 319 | Request you to kindly allow six weeks extension for submission of Bid from current date of 28th July, 2026.                                                                                                                                                                                                                                                                                                                                                                                          | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs                                                                                                                                                              |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                                              | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                             |
|-----|-----------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 246 | "Section-IX<br>Particular Conditions of Contract"<br>"Section-IX<br>Particular Conditions of Contract"                                  | We presume that the Recoveries for Equipment to be handed over to Contractor shall be recovered as Work Progresses and not in one go. Request you to kindly confirm whether our understanding is correct.                                                                                                                                                                                                                                                                                                                                                                                               | The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)).                                                                                                                                                                 |
| 247 | Section IX - Particular<br>ConditionsSub Clause 4.30                                                                                    | We respectfully request that the working capital deposit requirement be revised from three months' equated monthly Accepted Contract Amount to one month's equated monthly Accepted Contract Amount. Requiring funds equivalent to three months' contract value to be maintained in the Escrow Account would unnecessarily lock up significant working capital, thereby impacting the Contractor's liquidity and efficient deployment of financial resources for the Project. The proposed reduction would continue to provide adequate financial security while ensuring healthy cash flow management. | Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as "The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in an amount equivalent to one month of the equated monthly Accepted Contract Amount." |
| 248 | Scope of Work, p.134 (Plugging of<br>Diversion Tunnels); PC 4.29,<br>Milestones M1 (wk 54) and M9 (wk<br>212); Drg GEN-001, p.4; PC 8.5 | Please advise the current status and contractual completion dates of the diversion tunnels and river-closure works under the Pre-Construction Package, provide the PC 8.5 interface schedule, and confirm the Contractor's entitlement to Extension of Time and Cost if the tunnels are not completed on time and accordingly plugging of DT milestone will shift.                                                                                                                                                                                                                                      | The pre-construction works are scheduled to be completed within 10 months. In the event that the Diversion Tunnel (DT) works are not completed within this stipulated period, the subsequent work milestones shall be adjusted accordingly.                                                                                                                                            |
| 249 | PC 1.1.85, p.234; GC/PC4.12;<br>Works Requirements, Section 9; Sub-<br>Clauses 2.5 and 4.10                                             | Please confirm that: (a) all factual ground data (DPR stage and 2025-26 pre-construction drill logs, drift logs, geophysical surveys, and upstream/downstream cofferdam borehole logs) constitutes Site Data on which bidders may rely; (b) tunnel support will be remeasured against the rock classes actually encountered, without any cap; and (c) whether a Geotechnical Baseline Report will be issued.                                                                                                                                                                                            | All items to be executed in all geological conditions has been covered under BoQ and it shall be item rate.<br><br>Available GBR and GDR shared as Annexure: DCP-I(b)                                                                                                                                                                                                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                             | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                      | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                |
|-----|------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 250 | Drg DIV-002, p.7; BOQ BillA8; U/S cofferdam drawings                   | Please confirm that the cut-off wall will be remeasured to the depth actually reached; provide borehole data along the cofferdam axis and the grouting treatment applicable if bedrock is deeper than shown; review the BOQ quantity against the maximum 58 m / average 43 m depths; and confirm that the upstream working platform at EL 782 can be widened to 22-25 m for safe cutter operation.     | Available GBR and GDR shared as Annexure: DCP-I(b)The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period.                                                                                                                                         |
| 251 | TS Section B.20, Clauses 20.25.2(3) and (4); BOQ Items A20.1 and A20.3 | Please: (a) state the design cementitious content range for each RCC zone and increase the quantity of variation item A20.3 accordingly; (b) state the fly ash/pozzolana source and confirm who bears its cost within the PCC definition; and (c) set a time or event limit for release of the 2% hold-back if first filling is delayed by other packages, not later than the Performance Certificate. | a) Refer relevant IS code under Technical Specification for the cement specification and cementitious content. However, any variations shall be regulated in line with BoQ item A 20.3<br>b) It shall be the responsibility of the Bidder to confirm the source fulfilling required Specification.<br>c) Provisions of the Bid Document shall prevail.                                                                                    |
| 252 | PC 4.29, Milestones M2/M3,p.254; BOQ Item A20.1                        | Please state the placement programme and monsoon working assumptions underlying Milestone M3, confirm whether M3 will be adjusted for hydrological windows, confirm whether the designated quarry can supply approximately 150,000 tonnes of aggregate per month, and provide monsoon and working season data to enable methodology planning.                                                          | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. Rainfall Data has been already included in the Bidding Document and it shall be the responsibility of the Contractor to achieve the required aggregate output from the designated Quarry. |
| 253 | Works Requirements, Section 6.3, pp.148-149                            | Please clarify how quarry output will be apportioned between the two Contractors, and provide the royalty/lease costs, development obligations, dispute resolution mechanism, estimated available quantities, and aggregate quality and alkali-aggregate-reactivity test data.                                                                                                                         | Each Contractor shall be provided with a separate allocation within the same quarry for independent operation. During the operation phase, the Contractors with the Employer shall develop and implement a Standard Operating Procedure (SoP) to govern quarry operations.                                                                                                                                                                |
| 254 | PC Part B, Clause 19, p.258,8 item 7; BDS ITB 14.1                     | Please issue the Employer's CAR/TPPL policy terms (deductible schedule, exclusions and sub-limits) by addendum, clarify whether the deductibles apply per event or in aggregate, and                                                                                                                                                                                                                   | Owner Controlled Insurance Program under process and refer Section IX-Particular Conditions, Part B Special Provisions Sub Clause 19.1 and 19.2 for insurance requirements.                                                                                                                                                                                                                                                               |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                         | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|-----|--------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                    | confirm that a flood or GLOF during construction is an Employer's risk under Clause 17.2 with the Contractor's share capped at the stated deductible.                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| 255 | PC Part B, Clause 4.30, p.256; PC 14.7, p.278; Section III, 3(iii) | Please clarify: (a) how the Clause 4.30 working-capital deposit is calculated and when it falls due; (b) whether it earns interest and when it is released; (c) whether an unconditional bank guarantee may replace the cash deposit; and (d) whether the escrow arrangement can at any time block payments to suppliers or subcontractors. | Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as "The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in an amount equivalent to one month of the equated monthly Accepted Contract Amount."                                                                                                                                           |
| 256 | PC Part B, Clause 2.6, p.236; BDS ITB 14.1                         | Please confirm: (a) whether the Contractor is obliged to take over the listed equipment; (b) how, in what instalments and over what period the cost will be recovered; (c) the age, condition and warranty of each unit; and (d) how GST and import duty will be treated on the transfer.                                                   | It is mandatory for the contractor to take over all the minimum listed Employer's Equipment and the cost mentioned in Section IX- Particular Conditions, Part B-Special Provisions, Sub-Clause 2.6 shall be the applicable cost for the contractor and any additional cost shall be borne by the Employer. The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)) |
| 257 | Works Requirements, Section 6.8, p.150; Contract Data 4.19         | i) Is the estimated peak demand of 15 MW construction power includes pre- and post-cooling load of concrete (ii) the scope of additional construction power supply extension in the tender is limited to Low Voltage (LV) only. Pl confirm                                                                                                  | 15 MW peak demand includes the construction power requirement of the whole project.<br><br>The additional scope of tapping of line from 33 kV trunk line, if required along with transformer and LV supply will be in contractor's scope upon approval from the Employer.                                                                                                                                                                                                                                                        |
| 258 | BOQ Item A9.18 (p.9 of 26)                                         | Please confirm the correct unit and quantity for item A9.18 (Slush Grout). We understand the unit should be kg.                                                                                                                                                                                                                             | Unit of Measurement for the Line Item A9.18 Slush Grout under Annexure-4 Bill of Quantities (Page 10 of 26) is hereby changed to "kg"                                                                                                                                                                                                                                                                                                                                                                                            |
| 259 | BOQ Items A11.2.1 and A11.2.2 (p.10 of 26) vs A11.1                | Please verify and confirm the coupler quantities in items A11.2.1 and A11.2.2.                                                                                                                                                                                                                                                              | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| 260 | BDS ITB 7.2; RFB paragraph 8                                       | Please advise how and on which dates the Site Visit Certificate can be obtained, and whether site visits can be arranged for additional technical personnel and specialised subcontractors                                                                                                                                                  | The request for the site visit by the additional technical personnel after pre-bid meeting shall be facilitated by the Employer.                                                                                                                                                                                                                                                                                                                                                                                                 |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                        | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                   | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-----|---------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                   | representatives after the pre-bid meeting. Please also provide a site-visit / route-survey report to assess the feasibility of mobilising heavy equipment to site.                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 261 | Contract Data 8.8, p.231 vs PC Part B 4.29, p.255 | Please confirm which formula applies to milestone delays, confirm that the cap of 10% of the ACA covers milestone and completion damages together, and explain how the refund mechanism operates.                                                                                                                                                                   | Refer Section IX-Particular Conditions, Part A-Contract Data Sub-Clause 8.8 and any liquidated damages imposed for failure to achieve an earlier milestone shall be refunded upon issuance of the Milestone Completion Certificate by the Engineer, provided the Contractor achieves the subsequent milestone within the stipulated period.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 262 | PC Part B, Clause 8.5, p.267; GC 20.2; Clause 3.7 | We request that the quarterly time-bar in PC 8.5 be deleted or aligned with GC 20.2 (28 days from awareness), and confirmation that interface-delay determinations follow the Clause 3.7 determination process and are reviewable by the DAAB.                                                                                                                      | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 263 | BDS ITB 15.1; Contract Data14.15; BDS ITB 14.1    | Please confirm: (a) how and when the Employer will arrange convertible currency for hydro-mechanical components; (b) the process and timing for reimbursement or exemption of GST and import duties, in Bhutan and for supply routed through India; and (c) which Bhutanese withholding-tax rates (CIT/BIT and personnel PIT) are deemed included in the bid price. | (a) The Employer shall facilitate required convertible currencies for procurement of hydro-mechanical components and equipment by the Contractor as and when requested based on the progress of the work.<br>(b) The Custom Duty and GST Exemptions certificate shall be issued or reimbursed for imports of materials and equipment while GST amount shall be reimbursed for sourcing of materials within the country on submission of documentary evidence. The exemption applies strictly to direct input materials and equipment. For further details, refer Renewable Energy Tax Exemption Act of Bhutan 2026 (www.mof.gov.bt).<br>(c) The Bidder shall factor in the applicable withholding Tax Deducted at Source (TDS) in compliance with the Income Tax Act of Bhutan 2025 and Rules on the Income Tax Act of Bhutan 2025. |
| 264 | PC Part B, Clause 2.7, p.236 vs BOQ Annexure-4    | Please identify the BOQ line item through which the cost of Employer-provided residential facilities is recovered. If it is missing, please add it by                                                                                                                                                                                                               | The cost will be recovered from the contractor on a pro rata basis through the Interim Payment Certificate like mobilization advance (Section IX-Particular Conditions, Part B-Special Provisions Sub-Clause 14.2(a)).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                       | Addendum and Clarification                                                                                                                                                                                                                      |
|-----|-----------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                                       | addendum and state the recovery amounts and timing.                                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                 |
| 265 | BOQ Item A6.1.6 (p.5 of 26)                                                                                           | Please confirm the unit of measurement for item A6.1.6.                                                                                                                                                                                                                                                 | Unit of measurement is confirmed as Cum.                                                                                                                                                                                                        |
| 266 | Works Requirements, Clause 3.1, p.135 vs Scope of Work, p.134 vs TS B.22, Clause 22.12; Drgs DHPP-HM-DAM-2026-105/107 | Please confirm the correct clear opening (5.0 x 4.0 / 5.5 / 5.8 / 15 m) and sill level of the auxiliary spillway service gate, and issue a corrected, consistent data sheet and drawing so that leaf area, seal length, hoist capacity and BOQ quantities can be established on a single basis.         | The auxiliary spillway service gate of clear opening of 5.0mx5.8m with sill level at El.844.50 m                                                                                                                                                |
| 267 | TS 22.1.2 / 22.11.1 / 22.11.2 / 22.11.3.2 (Section B.22); Drgs DHPP-HM-DAM-2026-101/102                               | Please confirm, in a single consistent statement, the exact number of complete spillway stoplog sets (each of 7 elements) and elements to be supplied under BOQ Part 2, and complete the blank figure in Specification Clause 22.11.1.                                                                  | The number of stoplogs set has been confirmed as 1. The text (Particular Technical Specification (PTS) and BoQ) have been modified accordingly. Amended BoQ and PTS is attached as Annexure DCP-I(h) and DCP-I(i) respectively.                 |
| 268 | TS Section B.3, Clause 3.4(p.4 of 24); BOQ Items A9.7.1, Bills A4/A5                                                  | For an 11 m diameter drill-and-blast tunnel, please confirm whether the 100 mm pay-line allowance will be reviewed, and confirm that concrete filling of geologically accepted overbreak is paid under item A9.7.1, and support of such zones under Bills A4/A5, including behind liners in the tunnel. | A 100 mm pay line has been adopted as the standard, as full-face excavation of the 11 m tunnel section is not practicable. Considering the excavation methodology involving heading and benching, a 100 mm pay line is considered appropriate.  |
| 269 | Downstream cofferdam drawings                                                                                         | Please confirm the proposed working-platform level and the average cut-off-wall depth at the downstream cofferdam.                                                                                                                                                                                      | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. |
| 270 | Schedule of works                                                                                                     | Please specify the tentative commencement dates and schedule of both the upstream and downstream cofferdams to enable resource planning.                                                                                                                                                                | The Bidder is required to submit a detailed Construction Schedule, as per Section IV-Bidding Forms-Construction Schedule, adopting the proposed method statement and demonstrate the completion of DCP-I within the stipulated contract period. |
| 271 | BOQ Part 2, Item A22.4; TS 22.12.3.3, p.65; HM drawing set                                                            | Please provide the design basis, GA or preliminary schematic of the Environmental Flow Release System, including pipe routing, number and diameter, embedded parts, inlet trash rack and                                                                                                                | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                               |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                             | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                         | Addendum and Clarification                                                                                                                                                                                                 |
|-----|----------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                        | isolation/control valves, so that the lump sum can be priced; alternatively, convert it to measured items.                                                                                                                                                                                |                                                                                                                                                                                                                            |
| 272 | TS 22.11.4.4, p.56; TS 22.17, p.95; Drgs DHPP-HM-DAM-2026-101 to 104                   | Please provide an indicative developed surface area and the preferred material (or an indicative tonnage) for the spillway glacis, pier and breast-wall steel liner so that all bidders can price this weight-based BOQ item on a common basis.                                           | Please refer to the BoQ item A 22.1.6.1 for steel liner quantity in Kg. Detail design & drawing on associated minor items shall be covered only in detailed design drawings.                                               |
| 273 | Works Requirements, Clause 6.1.1, p.145; BOQ Item A23.1                                | Please identify the Employer-provided permanent access roads and bridges serving the DCP-I dam site, Adit-1, the quarries and the muck-disposal areas; Adit-1, the quarries and the muck-disposal areas; 40R?); and clarify how maintenance responsibility is shared with BOQ item A23.1. | Refer Annexure-5.1-Section-VII (Works' Requirement) under Clause 6 (Construction Facilities) on coverage of scope under BoQ Item No. A 23.1                                                                                |
| 274 | PC 4.29, Milestone M6, p.254                                                           | Please confirm whether Milestone M6 requires two or four radial gate sets to be delivered by week 180.                                                                                                                                                                                    | Replace the word "two (4) numbers" with "Six (6) numbers" under Section IX-Particular Conditions, Part B- Special Provisions Sub-Clause 4.29 (DCP-I-M6)                                                                    |
| 275 | Particular Technical Specs (PTS) 22.12.4.2, p.66 vs 22.11.4.2, p.55 vs 22.13.4.2, p.74 | Please confirm the intended seal material for the auxiliary spillway gate and stoplog (EPDM or SBR). If EPDM is acceptable or preferred, please provide the EPDM property requirements separately from the SBR properties so that compliant seals can be quoted.                          | Bidders may propose seals manufactured from either SBR or EPDM, provided that the selected material is suitable for the intended service conditions and complies with the applicable performance and quality requirements. |
| 276 | Drg DHPP-HM-DAM-2026-103                                                               | Please correct one of the two statements. In our experience the radius should be measured from the outside of the skin plate to ensure constant, uniform top-seal contact at every gate position; kindly confirm.                                                                         | The radius for the top-seal shall be measured from the outside surface of the skin plate to ensure constant, uniform seal contact at every gate position.                                                                  |
| 277 | Drg DHPP-HM-DAM-2026-104, Detail B                                                     | We recommend a field-proven spring-loaded (conveyor-belt type) lintel-seal arrangement, which accommodates thermal movement and eliminates the siltation risk. Please consider this arrangement and revise the drawing accordingly                                                        | Please refer to the technical specifications design data included in the bidding documents                                                                                                                                 |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                      | Clarifications Sought/Suggestions                                                                                                                                                 | Addendum and Clarification                                                                                                                                                                                                  |
|-----|-----------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 278 | Drg DHPP-HM-DAM-2026-104, Plan 807.2                            | Please provide adequate clear space between the arm and the pier for free cylinder movement and revise the drawing accordingly.                                                   | The details will be provided in the detailed design phase. Please refer to the BoQ, drawings, and technical specifications included in the bidding document                                                                 |
| 279 | PTS Clause 22.11.3                                              | Please incorporate the trunnion-bush design criteria (allowable stresses, casting type, alloy number and type of dry lubricant). The bush should be of the self-lubricating type. | The details will be provided in the detailed design phase. Please refer to the BoQ, drawings, and technical specifications included in the bidding document                                                                 |
| 280 | PTS Clause 22.11.3                                              | Please confirm the skin-plate material for the top-seal radial gate (stainless steel or stainless-clad).                                                                          | Please refer to the technical specifications where it is stated "The side, the top and the bottom sealing plates will be stainless steel. Each gate will be operated by two oil operated servo motors." (section 22.11.3.1) |
| 281 | PTS Clause 22.2.3, Sl. No.(c)                                   | Please add Devaglide, Lubrite, INA and GGB to the approved self-lubricating-bush vendors, as is common practice in comparable hydropower tenders.                                 | Please refer to the technical specifications design data included in the bidding document.                                                                                                                                  |
| 282 | PTS Clause 22.15.2                                              | Please provide the hoisting speed, long-travel speed and related parameters for the fixed wire-rope hoist and gantry crane.                                                       | Please refer to the technical specifications design data included in the bidding document.                                                                                                                                  |
| 283 | PTS Clause 22.13.2, p.72 vs Clause 22.13.3.1, p.73              | Please confirm which intake service-gate operating speed is correct.                                                                                                              | Please refer to the technical specifications design data included in the Tender Package. As per TS it is mentioned 1m/min +/- 5%                                                                                            |
| 284 | PTS Clause 22.14.2, p.81; Drg DHPP-HM-DAM-2026-109              | Please incorporate the TRCM boom radius in the specification and drawing.                                                                                                         | The details will be provided in the detailed design phase. Please refer to the technical specifications included in the bidding document.                                                                                   |
| 285 | PTS Clause 22.14.2, p.80; Drg DHPP-HM-DAM-2026-109, Key Section | Please correct one of the two trash-rack angles and revise the documents accordingly.                                                                                             | Technical specification clearly mentioned 10 degree. Please refer the drawings in tandem to the technical specifications included in the bidding document.                                                                  |
| 286 | PTS - permissible stresses                                      | Please include the permissible-stress criteria to be used in the structural design of the radial gates, vertical gates and embedded parts.                                        | Please refer to the technical specifications included in the bidding document.                                                                                                                                              |
| 287 | PTS - feeder points                                             | Please provide the number and locations of the feeder points for the hydro-mechanical equipment.                                                                                  | Feeder point shall be distributed from the Transformer point provided.<br>The additional scope of tapping of line from 33 kV trunk line,                                                                                    |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----|---------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | if required along with transformer and LV supply will be in contractor's scope upon approval from the Employer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| 288 | HM drawing set - plan views                                                           | Please revise the hydro-mechanical drawings to include plan views showing the equipment layout and distances.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | The exact location and plan view will be part of the detailed design. Please refer to the technical specifications included in the bidding document.                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| 289 | PTS - supply and control voltage                                                      | Please provide the supply and control voltages for the hydro-mechanical electrical system                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | The specifications currently identify 415/240 V AC, 50 Hz as the low-voltage distribution system and 220 V DC for gate alarms and limit-switch/control circuits.                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| 290 | PTS - electric motors                                                                 | Please provide the electric-motor details, including starting system, duty class and insulation requirements.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Electric motors shall generally be three-phase squirrel-cage induction motors complying with IEC 60034. Motors shall have Class F insulation with temperature rise limited to Class B and shall be rated for the duty class of the driven equipment. Direct-on-line starting may be used where verified by voltage-drop, starting-current, torque and thermal calculations; otherwise, an approved reduced-current starting method shall be provided. Drainage-pump motors shall be IP68 and S1 duty, while gate, hoist, crane and hydraulic-power-unit motors shall have duty ratings appropriate to their operating cycles. |
| 291 | BOQ Bill A19, Items A19.3 and A19.5 (Water Supply /and A19.5 (Water Supply /Sewerage) | Please confirm: (a) whether items A19.3 and A19.5 are permanent works for the Employer's operational use or temporary works for the construction workforce, together with the facility and location each item serves; (b) the design population to be adopted, or the specific Works Requirements / LMP clause that fixes it; and (c) the per-capita design loadings (water demand in litres/person/day and sewage generation), the treated-effluent discharge standard to be met, and any peak-factor or future-growth allowance, so that all bidders design and price these items on a common basis | This BoQ Item A 19.3 & 19.5 is meant for Operations & Maintenance phase of the Project and shall be installed in Dam top/Control room. Design parameters have been covered under Annexure- 5.1(Technical Specification) & its clause B.19.                                                                                                                                                                                                                                                                                                                                                                                    |
| 292 | Section IV - Bidding Forms, Method Statement', pp.68-69                               | Please confirm whether this is a drafting carry-over from the DCP-III bidding document, and issue the correct DCP-I-specific Method Statement and Construction Schedule                                                                                                                                                                                                                                                                                                                                                                                                                               | Second Paragraph of Section IV-Bidding Forms (Page 69 of 319) is amended as below: The Method Statement shall cover all aspects of the activities under DCP-I with special emphasize on the following points:1. River Diversion Management plan2.                                                                                                                                                                                                                                                                                                                                                                             |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                        | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|-----|--------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                              | requirement list before bidder commit resources to these scored, page-capped submissions.                                                                                                                                                                                                                                                                                                                                                                | Excavation Sequence of the Cofferdams (both U/s & D/s)3. Cut-Off Diaphragm Wall methodology4. Dam abutment stripping method 5. RCC placement method6. Excavation sequence of Heading & Benching Method for Head Race Tunnel7. Tunnel concrete lining arrangements8. Diversion Tunnels Plugging method9. Dewatering plan10. Curtain grouting plan11. Dam Instrumentation Plan12. Cycle time for Cofferdams, RCC & CVC concrete placement method for main dam and tunnel works with work fronts13. Manpower and material mobilization schedule14. Quality Control and Quality Assurance Plan15. Hydro-Mechanical gate erection plan16. Interfacing Plan for Civil and Hydro-Mechanical works17. Innovation and use of latest technology |
| 293 | Contract Data, Sub-Clause 14.7(b)(i) vs Section IX -Particular Conditions, amendment to Sub-Clause14.7(b)(i) | Please confirm which period governs interim payment. We note that, under the priority of documents, the Contract Data precedes Particular Conditions Part B.                                                                                                                                                                                                                                                                                             | Clause 14.7b(i) under Section IX-Particular Conditions Part A Contract Data is hereby amended as follows:"75% of the IPC within 7 days after the Engineer receives the Statement and supporting documents and the remaining 25% within 56 days after the Engineer receives the Statement and supporting documents."                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 294 | BOQ Part 2 (HSS Equipment), Category VI; Technical Specifications, Hydro-Mechanical Works chapter            | Please confirm the precise division of design responsibility for the hydro-mechanical works: does the Contractor carry detailed-design liability (as the BOQ Category VI wording implies), or is the Contractor's obligation limited to shop/fabrication drawings against a design issued by the Main Design Consultant? This affects professional-indemnity insurance pricing and the fabrication lead-time programme ahead of Milestones M4, M6 and M8 | Contractor's obligation is limited to shop/fabrication drawings against a design issued by the Main Design Consultant                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| 295 | Section VII - Works Requirements (mobilisation /no-objection provision), read with Sub-Clause 4.1            | Please confirm the maximum period within which the Engineer will respond to the Contractor's request for No-Objection to mobilise (haul roads, site establishment, geotechnical investigation works, and quarry/borrow development).                                                                                                                                                                                                                     | On fulfilment of Contractor's General Obligation under sub-clause 4.1 (Section-IX-Particular Conditions)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                   | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                    | Addendum and Clarification                                               |
|-----|--------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|
| 296 | BOQ Part 1, Items A1.1 and A1.2 (Section B.1 - Dewatering During Construction); TS dewatering payment clause | Please confirm the design inflow rates, ground water/seepage assumptions and hydrological basis used to derive items A1.1 and A1.2 so that bidders can verify these figures, and confirm our understanding that the quantities are Employer estimates only with no guaranteed minimum, while the quoted unit rate applies without cap to any actual quantity consumed, i.e. outside the normal Sub-Clause 4.11 / 12.3 quantity-variation and rate-review protection. | Provisions of the Bidding Document shall prevail.                        |
| 297 | Section VII - Works Requirements, Clause 6.9 (Source of Water Supply)                                        | Please share the KMZ file for the proposed site with the details stated in the tender document.                                                                                                                                                                                                                                                                                                                                                                      | KMZ file shared as Annexure: DCP-I(a)                                    |
| 298 | Section IX - Particular Conditions Part B (Special Provisions), Clause 14.2 (Advance Payment)                | We request that the mobilisation advance be increased to 10% of the Accepted Contract Amount, or alternatively that the amortisation rate be reduced from 10% to 5% of the amount of each IPC.                                                                                                                                                                                                                                                                       | Provisions of the Bidding Document shall prevail.                        |
| 299 | Section VII, Work Requirement-9.5 Construction Material & Technical Specification B.9 & B.20                 | There is mismatch of test result and TS requirement. Pl clarify.                                                                                                                                                                                                                                                                                                                                                                                                     | Technical Specification requirement shall prevail                        |
| 300 | Contractor's Representative and Key Personnel                                                                | (i) Kindly consider Class X with relevant experience of three years. (ii) kindly consider at least 50% of fresh VTI or class XII grade individual to upscale skill of locals, which will be in line to Local employment requirement of 30%.                                                                                                                                                                                                                          | Provisions of the Bidding Document shall prevail.                        |
| 301 |                                                                                                              | Requesting for issue of AUTOCAD file of tender drawing of DCP-I                                                                                                                                                                                                                                                                                                                                                                                                      | Contour Map of Project and General Layout shared as Annexure: DCP-I(c)   |
| 302 | Section-II, Bid Data Sheet, ITB 22.1                                                                         | We respectfully request an extension of four (4) weeks to the Bid submission deadline for both DCP-I and DCP-II, from 28th July 2026 to on or about 25th August 2026, pursuant to the Employer's discretion under ITB Sub-Clause 22.2 read with ITB Clause 8.                                                                                                                                                                                                        | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs |
| 303 | Section II- Bid Data Sheet, ITB 19.1- Bid security                                                           | We understand that as part of Bid security, bidder has to submit the unconditional Bank Guarantee.                                                                                                                                                                                                                                                                                                                                                                   | Section II-Bid Data Sheet Sub-Clause 19.1 is hereby amended              |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                                                    | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                    |
|-----|---------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                                               | <p>We request you to also consider the Insurance surety bonds along with the Bank Guarantee</p> <p>We request you to review and confirm.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | <p>"A Bid Security shall be required. Bid must be accompanied by a Bid Security in the form an unconditional bank guarantee from any financial institution in Bhutan and India. The amount and currency of the Bid Security shall be BTN/INR 248 million (Two Hundred Forty-Eight million) only."</p>                                                                                                         |
| 304 | Section III- Evaluation and Qualification Criteria4.2: Specific Construction & Contract Management Experience | <p>We submit that the qualification criteria outlined in the referred clause significantly limit the eligible bidders, as only a few entities currently meet the specified requirements of 85m high dam. In order to encourage wider participation and healthy competition, we also submit that the Indian Public Sector organization who are known for the development of similar type of contracts where dam is part of the project, also consider dam experience or experience of concrete quantities in place of Dam on pro rata basis in a single project from DAM or Water resources Project and not DAM alone. In this connection, we request that the qualification requirements may be amended as follows:(i) Experience of having constructed the dam of minimum height of 85 mORAchieved an annual progress of concreting of 0.50 million m3 in any one year in a Dam/Weir/Barrage/Water Resources Project in the last 20 yearsA Dam/Weir/ Barrages are also falls under water resources project category where the concreting technology is similar for other components in water resources project such as pump house., lining works, etc.</p> | <p>Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(i) is hereby amended as:<br/>"Experience of having constructed the dam of minimum height of 85 m and achieved an annual progress of concreting of 0.25 million m3 in any one year in a Dam/Weir/Barrage for River Diversion in the last 20 years.The Dam height and progress of concreting can be met through two separate projects"</p> |
| 305 | Section III- Evaluation and Qualification Criteria4.2: Specific Construction & Contract Management Experience | <p>We submit that the qualification criteria outlined in the referred clause significantly limit the eligible bidders, as only a few entities currently meet the specified requirements. In order to encourage wider participation and healthy competition, we also submit that the Indian Public Sector organization who are known for the development</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | <p>Section-III Evaluation and Qualification Criteria, Sub-Clause 4.2(ii) is hereby amended as:<br/>"Successfully achieved excavation for Dam/Barrage/Weir complex for River Diversion of minimum excavation volume of 0.80 million m3 in any one year in the last 20 years in the single project."</p>                                                                                                        |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                           | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                               |
|-----|--------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|
|     |                                      | of similar type of contracts where dam is part of the project also consider experience of Excavation Quantities on pro rata basis in a single project from DAM or Water resources Project and not DAM alone. In this connection, we request that the qualification requirements may be amended as follows:(ii) Successfully achieved open excavation for Dam/Weir/Barrage/Water Resources Project of minimum excavation volume 1.3 million m3 in any one year in the last 20 years in a single project.As the Excavation work technology adapted for the abutments & foundations for the Dam is similar to other components of water resources project.We request you to review and confirm |                                                                          |
| 306 | Section-II, Bid Data Sheet, ITB 22.1 | Considering the complexity, importance, and long-term impact of the project, we kindly request you to grant an extension of the submission deadline by 4 months from the current due date.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs |
| 307 | General Layout                       | Request the Employer to please provide KMZ File & the Auto Cad file.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | KMZ file shared as Annexure: DCP-I(a)                                    |
| 308 | Geotechnical Baseline / GBR          | Please confirm whether a Geotechnical Baseline Report, geological longitudinal section along the HRT/dam axis, and borehole data are available to bidders, since these materially affect pricing of excavation, rock support and grouting items (A2–A7).                                                                                                                                                                                                                                                                                                                                                                                                                                    | Available GBR and GDR shared as Annexure: DCP-I(b)                       |
| 309 | Geotechnical Baseline / GBR          | Kindly provide complete geological mapping of the dam foundation, intake, HRT and Adit.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                          |
| 310 | General Layout — Landslide Area      | A "Landslide Area" is marked adjacent to the alignment near the dam approach. Please confirm whether stabilization/remedial works in this zone are included in the DCP-I scope (e.g., under Item A17 – Slope Protection) or are excluded/covered under a separate package.                                                                                                                                                                                                                                                                                                                                                                                                                  | It is included in the scope under DCP-I                                  |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                        | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                           | Addendum and Clarification                                                                                                                                                                                                                                    |
|-----|-----------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 311 | General Layout — Settlement Areas | Several settlement/village areas (Tsamang, Chhali, Tsakaling, Saleng, etc.) are shown within or adjoining the project footprint. Please confirm the status of land acquisition/resettlement (R&R) for these areas and any consequent restriction on blasting, working hours, or haul routes near habitation.                                                | All Statutory Clearances like NOC from PAPs, Forest Clearance, Environmental Clearance, Land Acquisition and Livelihood Restoration Plan similar to Rehabilitation & Resettlement has been completed for the lands identified for the work under the Package. |
| 312 | General Layout — Access Roads     | Please clarify the scope split between "New Access Road" construction (shown in legend) and Item A23.1 "Repair and Maintenance of Access Road" (280 km-month). Is construction of new access roads included in DCP-I, or only repair/maintenance of existing roads? If new construction is included, please provide the BOQ pay item and drawing reference. | Provision under Section-VII: Works Requirement shall prevail                                                                                                                                                                                                  |
| 313 | Contractor's Facility Areas       | Please confirm whether the facility areas shown on the layout (construction facilities, batching plants, stockyards, muck dump areas) are indicative or are firmly allotted plots, whether they will be handed over free of cost/free of encumbrance by the Employer, and whether coordinates/boundary drawings for each area can be issued.                | Refer Information for Bidders under Section VII- Works' Requirement. Areas identified in Works' Requirement are firmly allotted plots.                                                                                                                        |
| 314 | Geotechnical Baseline / GBR       | Please confirm whether a Geotechnical Baseline Report, geological longitudinal section along the HRT/dam axis, and borehole data are available to bidders, since these materially affect pricing of excavation, rock support and grouting items.                                                                                                            | Available GBR and GDR shared as Annexure: DCP-I(b)                                                                                                                                                                                                            |
| 315 | Muck Disposal                     | Please confirm the environmental clearance status of the identified Muck Dump Areas, whether they are government-approved dumping sites, and whether the Contractor is required to obtain any additional statutory consent for disposal.                                                                                                                    | Clearance obtained.                                                                                                                                                                                                                                           |
| 316 | Seismic Design                    | Kindly provide seismic design parameters that need to be adopted.                                                                                                                                                                                                                                                                                           | Detailed Design will be undertaken by the Employer and seismic design parameters is not required at the current stage.                                                                                                                                        |




**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                            | Clarifications Sought/Suggestions                                                                                                                                                                                                 | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                                                        |
|-----|-------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 317 | Drawings                                              | Please provide BIM/3D geological model if available.                                                                                                                                                                              | Not available                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 318 | Payments                                              | Please clarify payment methodology for additional rock support ordered by Engineer                                                                                                                                                | Payment shall be regulated as per the provisions of Technical Specification & Bill of Quantities                                                                                                                                                                                                                                                                                                                                  |
| 319 | Grouting                                              | Please provide expected grout take & Kindly clarify payment for additional consolidation grouting ordered by Engineer                                                                                                             | Expected grout take to be considered from the available geological information provided. Payment shall be regulated as per the provisions of Technical Specification & Bill of Quantities                                                                                                                                                                                                                                         |
| 320 | Roads                                                 | Please confirm existing access road condition.                                                                                                                                                                                    | Refer Information for Bidders under Section VII- Works' Requirement.                                                                                                                                                                                                                                                                                                                                                              |
| 321 | Power                                                 | Please specify construction power availability & standby power responsibility                                                                                                                                                     | The availability of Construction Power is specified in the Bidding Document under Section VII-Works' Requirements Section 6.8 and standby power is the responsibility of Contractor by setting up appropriate DG Sets.                                                                                                                                                                                                            |
| 322 | Blasting                                              | Please clarify whether are there any blasting restrictions & Employer will facilitate explosive licences.                                                                                                                         | No blasting restrictions but need to issue advance notification for blasting date and time. No separate blasting licence is required to be obtained by the Contractor                                                                                                                                                                                                                                                             |
| 323 | Insurance                                             | Please specify Employer-insured risks & Please confirm CAR Insurance coverage.                                                                                                                                                    | Refer Section IX-Particular Conditions, Part B Special Provisions Sub Clause 19.1 and 19.2                                                                                                                                                                                                                                                                                                                                        |
| 324 | Hydrology                                             | Request the Employer to please provide the latest hydrological data including flood frequency analysis of the river                                                                                                               | River Discharge is provided as Annexure DCP-I(f)                                                                                                                                                                                                                                                                                                                                                                                  |
| 325 | Bidding document, Section II, Bid Data Sheet, ITB 4.1 | Bidder understands that the Experience criteria shall be evaluated based on Section III – Evaluation and Qualification Criteria.                                                                                                  | ITB 4.1 under Section-II Bid Data Sheet is hereby amended as "Maximum number of members including the Lead Member in the Joint Venture (JV) shall be 2 (Two). At Least one JV member shall have experience in construction of hydropower project in the Himalayan Region. For construction of head race tunnel, experience in construction of road tunnel, metros, railway tunnels in Himalayan Region shall also be acceptable." |
| 326 | Bidding document, Section II, Bid Data Sheet, ITB 45  | Clause states, "In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-1, DCP-II or DCP-II, the bidder shall be awarded only one package at the discretion of the Employer to the most | Section II-Bid Data Sheet Sub-Clause ITB 45 is amended as under:<br>The Employer will award the Contract to the successful bidder whose bid has been determined to be substantially responsive and has been determined as the Most Advantageous Bid.                                                                                                                                                                              |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                                        | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                                                    |
|-----|-----------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                                   | <p>advantageous bid.</p> <p>We request you to reconsider awarding at least two packages to the lowest bidder.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <p>In case, single lowest evaluated bidder is the lowest bidder for more than 1 package, i.e. in DCP-I, DCP-II or DCP-III, the Employer reserves the right to award more than one package to the same Bidder based on the most advantageous outcome for the Employer.</p>                                                                                                                     |
| 327 | Section IX – Particular Conditions of Contract, Sub-Clause 4.30 (Working Capital) | <p>Sub-Clause 4.30 requires mandatorily deposit and maintain in the Escrow Account a working capital amount equivalent to three months of the equated monthly Accepted Contract Amount. We would like to state that this is an additional financial burden on Contractor which will have significant adverse impact on the cashflow requirement during execution. Contractor respectfully requests the employer to review the requirement. Therefore, we propose instead of actual deposit the employer may seek credit facility certificates from the Bankers of the Contractor for this requisite amount which can be utilized during exigency. Kindly review our above proposal and amend this clause suitably.</p> | <p>Sub-Clause 4.30 Working Capital under Section IX-Particular Conditions, Part B-Special Provisions is hereby amended as""The Contractor shall mandatorily provide either (i) a Corporate Guarantee from its Parent Entity, or (ii) an unconditional Bank Guarantee, as working capital security, in an amount equivalent to one month of the equated monthly Accepted Contract Amount."</p> |
| 328 | Section II, Bid Data Sheet, ITB 22.1 – Bid Submission Deadline                    | <p>Given the sheer scale and complexity of this project, bidders need adequate time to conduct thorough site visits, finalize complex Joint Venture structures, and get accurate pricing from specialized vendors/consultants. Therefore, we request bid submission deadline be extended by a minimum of eight 2 months.</p>                                                                                                                                                                                                                                                                                                                                                                                           | <p>The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs</p>                                                                                                                                                                                                                                                                                                               |
| 329 | ITB 45 (Award of Contract for Multiple Packages)                                  | <p>ITB 45 states that a single lowest bidder can only be awarded one package to manage project risk. Our understanding is that this restriction applies only when the exact same bidding entity applies for multiple packages. Where a company bids alone for one package, but joins a Joint Venture (JV) for a different package, they are separate bidding entities. As long as the JV has its</p>                                                                                                                                                                                                                                                                                                                   | <p>Refer Section I- Instruction to Bidders Clause 4.3.</p>                                                                                                                                                                                                                                                                                                                                    |



**ADDENDUM AND CLARIFICATION-I for DCP-I  
(Dorjilung/CPD/DCP-I/2026/1200, 24th July, 2026)**

| SN  | RFB Clause                                                        | Clarifications Sought/Suggestions                                                                                                                                                                                                                                                                              | Addendum and Clarification                                                                                                                                                                                                                                                                                                                                    |
|-----|-------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     |                                                                   | own independent financial strength, equipment fleets, and teams to execute its work without overlapping with the individual bidder's resources, both entities are eligible to win their respective packages.                                                                                                   |                                                                                                                                                                                                                                                                                                                                                               |
| 330 | Section II, Bid Data Sheet, ITB 22.1 – Bid Submission Deadline    | Given the sheer scale and complexity of this project, bidders need adequate time to conduct thorough site visits, finalize complex Joint Venture structures, and get accurate pricing from specialized vendors/consultants. Therefore, we request bid submission deadline be extended by a minimum of 2 months | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs                                                                                                                                                                                                                                                                                      |
| 331 | General                                                           | Offload 20% of works to CDCL as in Khorlochhu Hydroelectric Power Project                                                                                                                                                                                                                                      | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                             |
| 332 | Section II- Bid Data Sheet, ITB 22.1                              | Extension of time for bid submission for a couple of weeks                                                                                                                                                                                                                                                     | The submission of the Bid is extended up to August 27, 2026 at 15.00 hrs                                                                                                                                                                                                                                                                                      |
| 333 | Section II- Bid Data Sheet, ITB 19.1- Bid Security                | Bid security amount is high. Request to substitute by Bid Securing Declaration                                                                                                                                                                                                                                 | Section II-Bid Data Sheet Sub Clause 19.1 is hereby amended as:"A Bid Security shall be required. Bid must be accompanied by a Bid Security in the form an unconditional bank guarantee from any financial institution in Bhutan and India. The amount and currency of the Bid Security shall be BTN/INR 248 million (Two Hundred Forty-Eight million) only." |
| 334 | Section III- Evaluation and Qualification Criteria, Clause No.1.4 | Can bring in manpower and equipment from Nepal                                                                                                                                                                                                                                                                 | Yes, subject to clearance from the relevant authority                                                                                                                                                                                                                                                                                                         |
| 335 | Section II- Bid Data Sheet, ITB 15.1                              | Can quote Bid in other convertible currencies other than Indian Rupee (INR)                                                                                                                                                                                                                                    | Provisions of the Bidding Document shall prevail.                                                                                                                                                                                                                                                                                                             |

